Compressed Air Magazine

SEPTEMBER 1947

STEEL SKELETON OF HUGE SIPHON

Framework for supporting concrete walls of water conduit in Washington

(Bureau of Reclamation Photo)

VOLUME 52 • NUMBER 9

NEW YORK • LONDON



THE *RIGHT* OIL CUTS OPERATING COSTS

USE THE *Texaco Alcaid, Algol or Ursa Oil* recommended for your particular compressors and operating conditions, and you'll enjoy peak efficiency plus rock-bottom operating costs.

Texaco Alcaid, Algol and Ursa Oils are specially processed to free them of impurities that form hard carbon and gummy deposits. They keep valves clean and active . . . assure free rings, open ports, clear air lines — extra hundreds of hours of trouble-free, full-pressure operation between overhauls.

A Lubrication Engineer will be glad to assist in selecting the *right* oil for your compressors. Just call the nearest of the more than 2500 Texaco distributing plants in the 48 States, or write The Texas Company, 135 East 42nd Street, New York 17, New York.

℞ FOR LONGER DRILL LIFE

Drill doctors everywhere prescribe Texaco Rock Drill Lubricants (E.P.) to prolong drill life. These "extreme pressure" lubricants resist wash-out, prevent rust in service or storage, protect parts fully under severest operating conditions. They are approved by leading rock drill manufacturers.

TEXACO

TEXACO Lubricants

FOR ALL AIR COMPRESSORS AND TOOLS

Tune in . . . TEXACO STAR THEATRE presents the TONY MARTIN SHOW every Sunday night. See newspaper for time and station.

STAYNEW PANEL FILTERS AVAILABLE IN THESE MAJOR TYPES...

USERS ENDORSE BOTH FOR HEAVY DUTY VENTILATION SERVICE

You can select a Staynew Filter—backed by 25 years of exclusive filter engineering experience—in either a DRY or a VISCOUS type. Both are heavily built, expertly designed units fulfilling the most exacting requirements of their respective applications. They provide outstanding performance in commercial and industrial installations. Full range of standard sizes in both types.



Filtering media to suit every requirement . . . easily cleaned . . . quick, inexpensive replacement of medium when required . . . greater filtering area . . . highly flame-resistant.



Dry Filter Cell Assembly



Large dust-holding capacity . . . medium arranged to provide "stage" filtration . . . unusually high dust removal efficiency . . . low resistance to air flow . . . unsurpassed cleaning ease.



Cross Section of Viscous Filter

IN CANADA: McCarthy and Robinson, Toronto, - Engineering Equipment Co., Montreal

COMPLETE DETAILS ON REQUEST

DOLLINGER CORPORATION

DOLLINGER PROTECTOMOTOR STAYNEW FILTERS

7 CENTRE PK., ROCHESTER 3, N. Y.

Representatives In Principal Cities

never underestimate your need for AIR

This fellow did! But someone may save him yet. Perhaps it's his first experience, or maybe he didn't heed the warnings.

Did you ever stop to consider how essential *Air Power* is to your shop or factory? And how Compressors, Air Tools, and air appliances do wear out eventually, or become inefficient in comparison with modern ones?

Have you found so many uses for *Air Power* that your compressors and piping are too small, making your workers use air at low, less-efficient pressures? Remember too, your plant has grown . . . methods have changed.

At present you may be using very little air, or perhaps none at all, but never overlook the tremendous possibilities and advantages of Air Power. *Never underestimate your need for Air.* Call in an Ingersoll-Rand Air-Power Specialist. He can help you.

77-1

COMPRESSORS • AIR TOOLS
ROCK DRILLS • TURBO BLOWERS
CENTRIFUGAL PUMPS • CONDENSERS
OIL & GAS ENGINES

Ingersoll-Rand
11 Broadway, New York 4, N. Y.

CONFIDENCE... how much is it worth?



IT WAS NINE YEARS before the first gasoline-driven automobile in the United States was operated by C. E. Duryea that the Brooklyn Bridge was opened in 1883. This fabulous engineering achievement was the culmination of over 26 years of planning and building, of bold vision and heart-breaking struggle, by John A. Roebling and his son Washington.

But the steadfast confidence of father and son in the success of their amazing venture is vindicated daily by the modern traffic this world-famous bridge continues to carry now . . . 64 years later.

How much is that confidence worth to you today . . . and to the John A. Roebling's Sons Company, now embarked on a multi-million dollar expansion program to meet the future's challenge?

Confidence is the driving power behind our efforts to make better products do better work for you.

You Can't Go Wrong—If You Use the Right "Blue Center" Rope

There's no better way to save wire rope dollars than to use the right rope for your job. That means the right grade of steel, the correct construction, the proper size. And your choice is easy when you specify Roebling "Blue Center" Steel Wire Rope.

In "Blue Center" you get what we feel sure is the finest rope steel made. Secondly, you have a wide range of constructions and sizes to choose from . . . in both preformed and non-preformed types.

Why not make the Roebling Field Engineer your right-hand man in selecting wire rope that will give you peak performance at the lowest overall cost? You can call or write him at our nearest branch office.



The *RIGHT* steel . . .

The *RIGHT* construction . . .

The *RIGHT* size . . .

—FOR YOUR JOB!

JOHN A. ROEBLING'S SONS COMPANY
TRENTON 2, NEW JERSEY
Branches and Warehouses in Principal Cities

Manufacturers of Wire Rope and Strand • Fittings • Slings • Screen, Hardware and Industrial Wire Cloth • Aerial Wire Rope Systems • Hard, Annealed or Tempered High and Low Carbon Fine and Specialty Wire, Flat Wire, Cold Rolled Strip and Cold Rolled Spring Steel • Ski Lifts • Electrical Wire and Cable • Suspension Bridges and Cables • Aircord, Aircord Terminals and Air Controls • Lawn Mowers

ROEBLING

A CENTURY OF CONFIDENCE

The most important advance in motor design in 58 YEARS...

★STANDARD INTEGRAL MOTORS, FRAMES 326 TO 203, NOW AVAILABLE FROM STOCK

Features and improvements demanded most by users ALL WRAPPED IN A SINGLE PACKAGE

When Westinghouse engineers began designing a postwar motor they abandoned the concept that all motors must be cousins. Instead, they asked electric motor users *what they wanted* in motors . . . features they couldn't buy in any one motor.

These features demanded most by motor users are *all* incorporated in the new Life-Line Motors:



ALL-STEEL PROTECTION. All frames, feet and brackets are HEAVY STEEL. Life-Line Motor stators are far stronger—a new core locking device eliminates rivets.

Westinghouse

PLANTS IN 25 CITIES . . . OFFICES EVERYWHERE

the New WESTINGHOUSE Life-Line MOTOR

It's completely new . . . it's completely different . . . it wraps up the advances made in "custom-built" wartime motors in a single package!

For 58 years, induction motors have been built fundamentally alike. Differences have been minor . . . improvements gradual. Today, in the new Life-Line, Westinghouse presents a major departure from accepted ideas of standard-motor limitations.

Life-Line, today, offers industry a truly all-steel protected motor. All exposed surfaces are HEAVY STEEL—frames of even the smallest sizes are 3/8" thick.

More compact power is packed in Life-Line. For example, on the 284 frame, size has been reduced 35%, although NEMA mounting dimensions have been maintained . . . starting torques are as much as 134% greater per pound of motor . . . maximum torques as much as 116% more per pound.

Electrical characteristics have been improved . . . new materials and new winding techniques give increased protection against electrical failure. And sealed, pre-lubricated bearings do away with need for greasing or attention for at least five years!

The Life-Line Motor, as a result, represents the biggest single step forward in design and construction since the invention of the electric motor 58 years ago. Life-Line Motors are now reaching the drives of industry by the thousands, but are not yet available in quantities to meet the unprecedented demand. So, look over Life-Line advantages now with an eye to your future requirements. Your local Westinghouse office can give you full details, or write to Westinghouse Electric Corporation, P. O. Box 2025, Buffalo 5, N. Y.

★ ★ ★

Life-Line Motors are now in production at the new Westinghouse Motor Works in Buffalo, N. Y. This plant is laid out, tooled and equipped to fully utilize newly developed production processes and techniques on a scale hitherto unequalled in the manufacture of electrical motors.

J-21406



LESS SPACE PER HP. Life-Line Motors occupy less space per horsepower than any other standard motor . . . making it easier to build into machines and install in cramped quarters.

MORE TORQUE PER LB. Life-Line Motors give as much as 134% higher starting torque per pound of motor . . . up to 116% higher maximum torque.



NO LUBRICATION FOR 5 YEARS. Life-Line Motors need no greasing for AT LEAST FIVE YEARS. Bearings are pre-lubricated . . . sealed against dirt and moisture.

IMPROVED WINDINGS. New insulating materials . . . new coil winding techniques . . . new stator slot designs . . . give the Life-Line new record-setting protection against electrical failures.

NEW QUIET SMOOTHNESS. Life-Line Motors cut vibration and noise to new low limits for standard motors . . . satisfy many "special motor" requirements.

NEW SLEEK LINES. The Life-Line has sleek lines . . . a smooth finish . . . discourages dust and dirt accumulations . . . harmonizes with modern machine and tool design.

Life-Line motors

Steam . . . water . . . oil . . . or gas
CRANE Supplies all Piping equipment

. . . A good thing to remember for a simplified piping job every time . . . on new or replacement installations. No matter what the fluid or working conditions, see the Crane line first for *all* piping equipment . . . and for dependable quality in every item.

For this water supply system, for example, the Crane Catalog puts everything at your finger tips . . . valves, fittings, pipe, and pipe line accessories. One order to your Crane Branch or Wholesaler covers all your needs. From design to erection to maintenance, your piping job moves fast and smooth . . . with good performance assured . . . because you get this 3-way advantage:

ONE SOURCE OF SUPPLY offering the world's largest selection of steel, iron, brass and alloy piping materials for all power, process, and general service applications.

ONE RESPONSIBILITY for piping materials—helping you to get the best installation, and to avoid needless delays on the job.

OUTSTANDING QUALITY in every item—assuring uniform dependability and durability throughout piping systems.

CRANE CO., 836 S. Michigan Ave., Chicago 5, Ill.
Branches and Wholesalers Serving All Industrial Areas

ONE
SOURCE OF SUPPLY
RESPONSIBILITY
STANDARD OF QUALITY



Typical hookup for industrial water supply system; all piping equipment from Crane.

(Right) **FACTS YOU SHOULD KNOW** *about Crane Standard Iron Body Wedge Gate Valves. Improved body design reduces weight, yet increases strength. Straight-through ports assure streamline flow. Shoulder-type seat rings keep seating tight. Crane yoke design means smooth operation and easy maintenance. Patterns for every need; brass-trimmed or all iron; sizes 2 in. and larger. For steam pressures up to 125 pounds; for cold services up to 200 pounds. See your Crane Catalog, pp. 101 to 106.*

EVERYTHING FROM . . .

CRANE

VALVES • FITTINGS
PIPE • PLUMBING
AND HEATING

FOR EVERY PIPING SYSTEM

RockerShovel Loading at Eldorado Limestone



The Eldorado Limestone Mine at Shingle Springs, California, use their Model 21 RockerShovel for loading from drawholes in an elaborate shrinkage stope setup. In conjunction with their loader they have developed a "turntable" car for quick transportation of the loader and ease in turning the machine for loading from drawpoints on either side of the main haulage way.

The RockerShovel has been adapted to many mining systems. Its rugged construction, simple operation and dependability make it the favorite loading equipment for mining men the world over.

Speed, power and efficiency of the RockerShovel make it an unbeatable tool for underground service.

Write for more information on Eimco RockerShovels.



EIMCO

THE EIMCO CORPORATION

The World's Largest Manufacturer of Underground Rock Loading Machines

Executive Offices and Factories — Salt Lake City 8, Utah: Branches — 67 Wall St., New York 5 — 3319 So. Wallace, St., Chicago 16—Mills Bldg., El Paso—1217 - 7th St., Sacramento 14



The smooth center hole in Bethlehem Hollow Drill Steel does not just happen that way. Metallic cores of accurate size are inserted into the drilled billets of carbon tool steel which have passed scrupulous inspection. The billets are then reduced to bars of proper size and shape by precision rolling over the core, which when withdrawn leaves a smooth, uniform hole.

There are many other considerations in producing fine drill steel, but it *is* important that the hole be free from imperfections which lead to fatigue-failure and premature breakage. And any drill runner knows how drilling slows up when the hole is not true.

Hard-rock men want drill steel they can rely on. That's probably why so many insist on Bethlehem Hollow. It means more feet drilled per shift, whether you use detachables or forged-on bits. Next time ask for Bethlehem Hollow, not just "drill steel."

BETHLEHEM STEEL COMPANY, BETHLEHEM, PA.

On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation

BETHLEHEM HOLLOW DRILL STEEL

BETHLEHEM STEEL

A1012



TYPICAL of big EASTON dump trailers for mines and quarries is the rugged Model TD which features an automatic down-folding side door. Capacities up to 40 tons.

TO MOVE *BIG* LOADS AT LOW COST...

EASTON *Trailers*

PORTABILITY is the advantage featured in this specially designed EASTON trailer, which mounts a 1500 gallon chemical storage tank.

Speed, flexibility, lower costs, and the ability to move bigger loads with less power—these are some of the advantages which have helped to introduce the trailer idea to mines, quarries, industrial plants and other off-highway haulage operations. Application of the proved advantages of big, pneumatic-tired trailers to new fields of off-highway service has followed the initiative of foresighted plant operating executives. Men who want to move bigger loads at lower cost will envision new opportunities to save with big, off-highway trailers. Easton will design and build these trailers.

Easton Car & Construction Company, Easton, Pa.

ALL TYPES OF HEAVY-DUTY INDUSTRIAL CARS • TRAILERS • TRUCK BODIES • ELECTRIC TRUCKS



Here is
ANTI-FRICTION COMPRESSOR PERFORMANCE
at its best

Tapered Roller TIMKEN BEARING EQUIPPED

This Ingersoll-Rand 7 x 7 ES-1 air compressor is equipped with Timken Tapered Roller Bearings on the crank shaft. Many years of compressor experience have proved that Timken Bearings meet every anti-friction requirement with utmost efficiency.

They eliminate friction and wear; carry radial, thrust and combined loads; and hold moving parts in correct and constant alignment. Furthermore, being made of Timken Fine Alloy Steel developed and produced in our own steel plant, Timken Bearings possess maximum strength and endurance under all conditions of service.

If you do not get all these advantages in your new compressor, you will not be getting anti-friction performance in full. To make sure of getting it, buy "Timken Bearing Equipped".

THE TIMKEN ROLLER BEARING COMPANY, CANTON 6, OHIO

TIMKEN
TRADE-MARK REG. U. S. PAT. OFF.
TAPERED ROLLER BEARINGS

NOT JUST A BALL ◯ NOT JUST A ROLLER ⬭ THE TIMKEN TAPERED ROLLER ⬭ BEARING TAKES RADIAL ⊖ AND THRUST ⊖ LOADS OR ANY COMBINATION ✳

3600 R. P. M. FOR CENTRIFUGAL PUMPS, COMPRESSORS AND BLOWERS . . .



BUILT STRONG TO LAST LONG AND RUN *trouble-free!*

E-M's NEW HEAVY-DUTY SQUIRREL-CAGE INDUCTION MOTOR

Large boiler feed pumps and oil pipeline pumps demand the highest degree of continuous reliable performance from their motor drives. The exacting requirements of high-speed service are met in the NEW, modern E-M Heavy-Duty Two-Pole Squirrel-Cage Induction Motor. Incorporating all the important advances in modern motor design and construction such as listed at the right, this new E-M motor provides extra features for dependability in continuous service. Heavy-duty construction forestalls breakdown. Protective design encourages preventive maintenance. Selection of this E-M motor assures years of trouble-free performance for high-speed pumps, compressors and blowers.

Send the coupon for descriptive literature.

DRIP-PROOF—Protective construction guards against falling liquids and particles. Streamlined exterior is easy to keep clean.

STEEL FRAME—Strong without excessive weight. Steel bar feet that cannot crack.

EXTRA TOUGH COILS—Form-wound, multi-layer insulation, varnish impregnated, moisture resistant, firmly braced coil-ends.

MINIMUM NOISE—Magnetic circuit designed for quiet operation. Windage noise minimized. Double-end specially engineered ventilation moves abundant air at low velocity.

PHOS-COPPER BRAZE-WELDED CAGE WINDING—designed to keep expansion and contraction within elastic limits of cage bars and end-rings.

LEAK-PROOF, DUST-PROOF BEARINGS—Ground journals, cool running, easily accessible. Kolene-Process, centrifugally-cast sleeves insure uniform babbitt free from blow-holes.

STRONG, STIFF ROTOR—Core punchings stocked on shaft and held between welded pressure plates; extra-large diameter, carbon steel shaft has first critical speed well above running speed.

E-M

ELECTRIC MACHINERY MFG. COMPANY • MINNEAPOLIS 13, MINNESOTA

Please send me your six page colored booklet, "E-M Two-Pole Heavy-Duty Squirrel-Cage Induction Motors" and foldout sheet detailing construction.

Name_____

Firm_____ Address_____

City_____ Zone_____ State_____

A 2047

A JOB FOR A LONG-TERM SHOVEL

Loading iron ore on the Mesabi Range places extra premium on the 5-yard 120-B's longest suit—ability to deliver a long-term average of high production and economy. Massive strength, minimum weight, high speed cycle, low power consumption, these are some of the features that keep Bucyrus-Eries "years ahead."

211-46



For *Sustained* High Production at Low Cost...

BUCYRUS ERIE

SOUTH MILWAUKEE, WIS.

They're Ready

REVOLUTIONARY CARSET JACKBITS



You have been hearing about the new Ingersoll-Rand CARSET bit with *CARBOLOY* cutting edges. Here it is—an alloy steel bit with cutting edges of tungsten carbide, the hardest metallic substance made by man. Although developed with heavy drifters and high air pressures, the Carset Jackbit is in keeping with, and ideally suited to, the modern trend toward smaller machines and smaller holes. The amazing performance of this new *ultra-hard tipped* bit is due in part to its use with the recently announced "Jackstud" bit connector. Reports from mines and tests in our development work indicate the Carset bit to be one of the greatest advances in rock drilling history. We are confident that the Carset Jackbit opens the door to a new era in rock drilling. Performance and specific advances read like a driller's dream.

FOR INSTANCE, YOU CAN—

Drill continuously with one size bit
Use steels as long as the setup will permit
Increase drilling speeds 20% and higher
Almost eliminate the changing of bits
Drill small, uniform diameter holes
Materially reduce explosive costs
Drill the hardest rock
Reduce or even eliminate bit reconditioning
Use lighter drills
Drill more holes with the same amount of air
Finish more rounds per month

Order some Carset Jackbits and Stud Jackrods now and determine the economics of their use in your own operation.

CARSET JACKBIT after drilling 307 FEET

in Barre Granite with a DA-35 Drifter at 90 psi

Ingersoll-Rand

36-15 11 BROADWAY, NEW YORK 4, N. Y.

FOR LONG, CONTINUOUS SERVICE



. . . leather belting is a "natural"



The pivoted motor base provides continuous, automatic control of belt tension.

Leather belting's *natural* stamina and durability are the reasons why it has piled up long service records on compressor drives.

There's no special traction surface added to wear off with resultant loss in efficiency. It's leather . . . resilient, flexible, pulley-gripping leather, *all the way through*. Leather belting has natural ability to absorb shocks and carry heavy loads at lower tensions.

For continuously efficient, trouble-free service, use leather belting on your compressor drives.

AL-5



American **LEATHER BELTING** *Association*

Headquarters for Authentic Power Transmission Data

41 PARK ROW, NEW YORK 7, NEW YORK

IS THIS THE Oldest Burke M-G SET IN SERVICE TODAY?



Burke 200 KW, 500 RPM, M-G Set with 300 HP 2200 V., 3 phase Induction Motor driving, 200 KW, 230/240 V. Generator, installed in 1907.

"GENTLEMEN:

I was employed by the Pittsburgh Plate Glass Company here in Crystal City on September 22, 1909, one of my first jobs was the inspection of the Burke M-G Set which was purchased in 1907. This was one of my duties for several years during which time I changed a few brushes, smoothed the commutator with fine sandstone and changed bearing oil.

We used this unit on a narrow gauge railway where several electric locomotives were operating and where the current was up and down. I was always very much interested in this generator set and on my usual rounds every day to the power house I checked various operating units and I must say that this generator could and did take some high current punches.

In 1926 we rewound the AC end here at this plant for 550 volts, 3 phase, 60 cycles and it was then shipped to our Ford City plant, Works No. 4, for use in the machine shop.

In 1944 it was changed back to 2300 volts, 3 phase, 60 cycles, and it has been in service at our sand mines since that time.

To my personal knowledge the commutator on the DC generator of this Burke unit was never turned in the lathe and only a few brushes changed when they were a little short or occasionally a brush holder was changed because of a weak spring.

Yours truly,
P. E. MAHEW
Chief Electrician"

40 years of Service in 2 Plants and Still Operating Smoothly

EARLY in 1947 we honored several new members of the Burke Quarter-Century Club and thought it entirely fitting to seek out and recognize likewise the oldest Burke electrical unit and its supervisor. Actually the M-G set illustrated above was among the first major products to bear the Burke nameplate. Prior to 1907, our parent company was known as Keystone Electric Co.

We believe with the above 40 year user we have found the oldest Burke unit in service today, but to make certain we are extending our search to October 1, 1947. We have discovered many Burke units during this search that have served 20 or more years which gives Burke men and women real satisfaction in knowing that their good workmanship is reflected in the long service records of Burke Equipment.

BURKE ELECTRIC COMPANY 2079 W. 12th ST. ERIE, PA.

UNIVERSAL MOTORS 1/50th to 1½ HP	SINGLE PHASE MOTORS to ½ HP	INDUCTION MOTORS 1 to 1500 HP	SYNCHRONOUS MOTORS to 1500 HP GEN. to 1000 Kw.	TERMINAL BLOCKS 10 TYPES	D.C. MOTORS to 1500 HP GEN. to 1000 Kw.	M-G SETS to 1000 Kw.	HIGH CYCLE M-G SETS— 7 STD. SIZES



For High-speed

Low-cost Production



YOU'LL find suggested specifications for the new fast cutting, long lived B-5 and B-7 resinoid wheels for grinding castings of steel, malleable iron (annealed and unannealed), gray iron, brass, magnesium and aluminum on floor stands, swing frames, portables and disc grinders.

Included also are specifications and list prices on mounted points, cut-off wheels, rubbing bricks, and core files. There's a [illegible] on grinding wheel dressers and handy table of grinding wheel speeds.

If you haven't a copy of this new edition send the coupon.

NORTON COMPANY • Worcester 6, Mass.

Please send a copy of the new edition of your catalog of grinding wheels for the foundry.

Name ..... Title .....

Firm .....

Street .....

City ..... Zone ..... State .....

W-1117

Compressed Air Magazine

COPYRIGHT 1947 BY COMPRESSED AIR MAGAZINE COMPANY

VOLUME 52 **September, 1947** NUMBER 9

G. W. MORRISON, *Publisher*

C. H. VIVIAN, *Editor* J. W. YOUNG, *Director of Advertising*
ANNA M. HOFFMANN, *Associate Editor* J. J. KATARBA, *Advertising Mgr.*
A. W. LOOMIS, *Assistant Editor* DON J. MAREK, *Advertising Sales*
D. Y. MARSHALL, *Europe*, 243 Upper Thames St., London, E.C., 4.
F. A. MCLEAN, *Canada*, New Birks Building, Montreal, Quebec.

EDITORIAL CONTENTS

Under the Bay to Brooklyn—*R. G. Skerrett* 210
Princeton University's Unique New Library—*C. H. Vivian* 217
Keys to Everything—*Allen S. Park* 223
Compressed Air at Work 226
Editorials—Brooklyn-Battery Tunnel—Birthday of U. S. Irrigation 228
This and That 229
Machine Removes Scale from Welded Axle Housings 230
New Army Air Dreadnought 230
Sound Waves Inspect Metal 230
New Books 231
New Process Forecasts Wider Use of Titanium 232
Industrial Notes 233

ADVERTISING INDEX

Air-Maze Corp. 36
Allis-Chalmers Co. 28
American Leather Belting Assn. 16
Bethlehem Steel Co. 10, 30
Black, Sivalls & Bryson, Inc. 37
Bucyrus Erie Co. 14
Burke Electric Co. 17
Combustion Engineering Co. 23
Compressed Air Magazine 40
Conrader Co., R. 38
Cook Mfg. Co., C. Lee 27
Crane Co. 8
Cuno Engineering Corp. 22
Dollinger Corp. 3
Easton Car & Construction Co. 11
Eimco Corp., The 9
Electric Machinery Mfg. Co. 13
Fairbanks Co., The 41
Galland-Henning Mfg. Co. 39
General Electric Co. 31, 32
Industrial Clutch Corp. 35
Ingersoll-Rand Co. 4, 15, 24, 33
Leavitt Machine Co., The 40
Maxim Silencer Co., The 36
National Forge & Ordnance Co. 21
Naylor Pipe Co. 19
New Jersey Meter Co. 39
Nicholson & Co., W.H. 37
Norgren Co., C.A. 38
Norton Co. 18
Rhoads & Sons., J. E. ..... 3rd Cover
Roebling's Sons Co., John A. 5
Schieren Co., Chas. A. 38
Socony-Vacuum Oil Co., Inc. ..... 4th Cover
Square D Co. 37
Terry Steam Turbine Co., The 29
Texas Co., The ..... 2nd Cover
Timken Roller Bearing Co., The 12
Victaulic Co. of America 20
Vogt Machine Co., Inc., Henry 34
Wagner Electric Corp. 26
Walworth Co. 25
Wisconsin Motor Corp. 36
Westinghouse Electric Corp 6, 7

A monthly publication devoted to the many fields of endeavor in which compressed air serves useful purposes. Founded in 1896.

CCA Member Controlled Circulation Audit

Published by Compressed Air Magazine Co., G. W. MORRISON, *President*; C. H. VIVIAN, *Vice-President*; J. W. YOUNG, *Secretary-Treasurer*.
Business, editorial, and publication offices, Phillipsburg, N. J.
Advertising Office, 11 Broadway, New York 4, N. Y., L. H. GEYER, *Representative*.
Annual subscription: U.S., $3.00; foreign, $3.50. Single copies, 35 cents.
COMPRESSED AIR MAGAZINE is on file in many libraries and is indexed in Industrial Arts Index.

ON THE COVER

TO DISTRIBUTE water stored behind Grand Coulee Dam to arid land in the Big Bend section of Washington State, it will be necessary at one place to cross a dry coulee. This link in the conduit will take the form of a 4400-foot siphon. It is now being built for the U. S. Bureau of Reclamation by the Utah Construction Company of San Francisco and Winston Brothers of Los Angeles Calif., as a part of a $2,871,796 contract for the first 6½ miles of the 88-mile West Canal. The latter will carry water to 281,000 acres in the western part of the million-acre Columbia Basin Project. Our cover picture shows multiple steel hoops 84 feet in circumference that will serve as ribs for the 2-foot concrete shell of the siphon. In the background are forms for pouring concrete. Viewing the work is a project visitor, Col. G.Y.L. Crossley, field representative of the Bureau of Reconstruction, Government of British Columbia.

•

IN THIS ISSUE

AS THE years pass, New Yorkers spend more and more of their time underneath the earth's surface. If you are on foot in Gotham and want to go anywhere in a hurry you ride the subway, which hurtles you along at around 40 miles per hour, oblivious of traffic congestion in the streets overhead. There was a time when motorists bound to or from insular Manhatten, key borough of the city, used bridges or ferries. Now there are two subaqueous tunnels connecting with the New Jersey shore and one with the Borough of Queens. A fourth twin-tube thoroughfare, which will be larger than any of these, is now being driven under the bay to Brooklyn. Our leading article is the first of two describing its construction. The second part will appear in October.

•

BUILDING a library such as the one that is now taking form at Princeton University can be almost a lifework. A good many persons have spent an appreciable amount of their time for the past twenty years laying the groundwork for the 6-million-dollar structure. It embodies many innovations and will, perhaps, set a pattern for future libraries on college or university campuses. See page 217.

•

IF YOU'VE lost a door or car key, perhaps the finder has sent it to Baldpate Inn, a mountain hotel in Colorado. At any rate, we'll wager you could find a duplicate there among the 10,000 and more that constitute the largest collection of keys outside of a key factory. See page 223.

Under the Bay to Brooklyn

R. G. Skerrett

Part I

ILLUSTRATIONS FROM TRIBOROUGH BRIDGE & TUNNEL AUTHORITY



MISCELLANEOUS VIEWS

The white patch on the water's surface in the picture at the right is compressed air escaping from the heading of one of the tubes being driven northward from Brooklyn toward Manhattan, whose skyscrapers are in the background. Visible at the upper right is a part of Brooklyn Bridge—the first vehicular travelway between the two boroughs that are now being connected by another underwater artery. In the circle is an artist's drawing of the ventilation building that will stand about midlength of the two tunnels. It will occupy a man-made island just offshore from Governors Island. In driving the headings from Brooklyn, it has been necessary in places to lay a blanket of clay on the bay bottom to increase the cover over the compressed-air shields to a safe thickness. When no longer needed, the clay was removed. This was usually done by dredging, but along one stretch this procedure would have disturbed or broken water lines and electric conduits running to Governors Island. Consequently, the clay was first broken up with jets of compressed air and then pumped into barges by means of air lifts. The view just above shows this work in progress, with a portable compressor that supplied the necessary air.

NEW YORK CITY'S fourth and longest twin-tube, subaqueous vehicular highway is nearing its most momentous construction stage—the "holing through" of the oppositely advancing headings at a point in midstream more than 100 feet below the surface of the swift East River. But for World War II, the tunnel and its terminal features would have been finished and opened to traffic in the fall of 1944; and thousands of drivers of automotive vehicles between the southern tip of Manhattan and the neighboring shore of Brooklyn would be enjoying the benefits of another engineering triumph. As it is, sustained efforts will be needed to complete the project some time in 1949.

Next year will mark the semicentennial of the consolidation of the separate areas that form the City of Greater New York—the five boroughs of Manhattan, Brooklyn, The Bronx, Queens, and Richmond. That union was first urged in 1868 by Andrew H. Green, a public-spirited citizen of Brooklyn, but did not become a reality until 30 years later. With that amalgamation, New York's growing pains began in earnest, only to become recurrent with varying intensity. Such was the natural outcome of an abruptly and vastly enlarged body politic and its readjustment as a single community with reciprocal interests and interrelated material needs. A civic celebration will commemorate the Golden Jubilee, and then the populace will perhaps become fully aware of some of the reasons for the successive construction of the Holland, the Lincoln, the Queens-Midtown, and the Brooklyn-Battery tunnels—all consequences of the city's continual growth and need for more and still more rapid-transit facilities.

In 1900, two years after the consolidation, Greater New York had a population of 3,437,202, as follows: Manhattan, 1,850,093; Brooklyn, 1,166,582; The Bronx, 200,507; Queens, 152,999; and Richmond 67,021. Today, there are an estimated 7,835,000 persons in the boroughs, and the way they are distributed gives a hint of one major cause for the continually mounting transportation and traffic problems. Brooklyn now has

2,798,000 inhabitants—892,000 more than Manhattan, which is a long and relatively narrow island and the smallest of all the boroughs. The Bronx and Queens are close competitors, having 1,489,000 and 1,456,000 residents, respectively, and each aspires to outstrip Manhattan in numbers. Even so, the latter maintains her financial and business dominance, which is historic.

Every working day the island is the goal for an immense influx of people not only from the neighboring boroughs but from outlying counties in New York State and from Connecticut and New Jersey. The majority of these migrants surcharge the rapid-transit facilities every week-day morning and late afternoon, but the greatest present difficulty is to provide more and ampler ways to accommodate the automotive vehicles entering and leaving Manhattan and threading its thoroughfares so that they can travel faster and with less frequency of congestion.

In the interval between 1924 and 1942, before the war crimped motor-car production, the registered vehicles in Greater New York increased from just short of 430,000 to more than one million. No wonder Manhattan's few main traffic arteries are suffering from high pressure. The Brooklyn-Battery Tunnel, which will handle an estimated 16,000,000 vehicles annually, should prove of great aid in ameliorating the rush-hour flow over the three lower bridges that link the island and Brooklyn.

Preliminary plans for the Brooklyn-Battery Tunnel were drafted in 1929, but it was not until June of 1936 that the project was approved and a sum of $75,000 made available to the New York City Tunnel Authority for conducting certain advance investigations, for making borings, and for the submission of a report. On the basis of data contained in the latter and on continued studies, the undertaking won increasing favor; but financial conditions were becoming more and more disturbing. That fact, together with the great cost of such an engineering project and the length of time required to complete it, postponed actual beginning of the work.

It was not until June 28, 1940, that funds were appropriated. Then the Reconstruction Finance Corporation made a loan of $57,000,000 for "the plaza to plaza construction of the river crossing, under condition that the City agree to purchase the necessary real estate and that the City and Triborough Bridge Authority agree to construct certain connections in Manhattan and Brooklyn." Ceremonial ground-breaking on October 28, 1940, at the Brooklyn site of the two construction shafts, in which the late President Roosevelt participated, officially marked the start of tunneling operations. Sinking of the shafts was done by Andrew Catapano, contractor. But before telling how work on the tunnel has been done and has progressed, one should know something about the principal features of this outstanding undertaking—so little of which is yet in evidence above ground.

The Brooklyn-Battery Tunnel, like the three other subaqueous vehicular crossings built for the Metropolis, will consist of two tubes, one for northbound and one for southbound traffic to avoid confusion and, in each case, to permit two lines of vehicles to move rapidly in the same direction. Where they underrun the river, each has an outside diameter of 31 feet, as compared with the Holland Tunnel's 29 feet 6 inches. Between terminal plazas, the new tunnel has a designed length of 11,100 feet, or 2.1 miles. It is ¼ mile longer than the Holland Tunnel under the Hudson River and exceeds by more than ½ mile the length of the Queens-Midtown under the East River.

Between portals, the Brooklyn-Battery Tunnel travels under land and water for a stretch of 9117 feet, or about 1.7 miles. It traces a direct and smoothly bending course between the Manhattan plaza, a little more than 2200 feet inland from the pierhead line, and that on Hamilton Avenue in Brooklyn. The latter plaza, 3000 feet inland from the pierhead line, has been kept well clear of that borough's waterfront and the expected further development of its important shipping and allied interests. Because of the long distance between portals, ample ventilation will be assured even under conditions of densest traffic by a blower building at the Manhattan portal, a ventilation building in midriver close to Governors Island, and another ventilation building near the Brooklyn portal.

The Manhattan plaza occupies a block just north of Battery Place at the southern tip of the island where old residential structures, long in a state of degeneration, had stood in dingy contrast to towering office buildings. It will serve



vehicular traffic in a number of ways, forming, as it will, an extension of the West Side Express Highway, an elevated route for fast-motor traffic; a street-level connection; and a link in East River Drive that reaches South Ferry via South Street which parallels the East River waterfront in that section of the city.

The connection between the Brooklyn-Battery Tunnel and East River Drive or the West Side Express Highway will be by underpass curving around beneath Battery Park so as to avoid the slow-moving or halted surface vehicles bound to and from the docks of ferries plying between Manhattan and Staten Island. Reference to an accompanying plan makes the layout of these links understandable. At the Brooklyn plaza there will be under- and overpasses, as well as street-level connections to promote easy and rapid movement of traffic entering and leaving the tunnel. One of these engineering features is to be an express link with the Brooklyn Shorefront Highway.

The design of the Brooklyn-Battery Tunnel is based in principle upon what was done and learned during the construction of the Holland Tunnel, which was started in 1920 and opened to traffic on November 13, 1927. That twin tube had been preceded in the Port of New York by other underwater tunnels built to facilitate railway transit beneath the Hudson, the East River, and the Harlem River; but vehicular traffic, and especially motor-driven traffic, introduced new problems, particularly that of adequate ventilation at all times. In design, construction, building methods, and facilities, the Holland tubes represented numerous innovations and betterments, and the metropolitan subaqueous vehicular tunnels that have followed typify the progress made and the skill of the men engaged in that line of work.

Before the final line of the tunnel between the Battery and Governors Island was determined by exploratory drilling, the route had been projected at a higher level which would have required excavating for some distance through mixed ground with its inherent difficulties. However, borings disclosed that the rock formation lay considerably closer to the ground surface than had been expected and that by dropping the line sufficiently an adequate cover of Manhattan schist would permit driving full-rock tunnel sections from the Battery to a point about 1000 feet south of

RECOMPRESSION CHAMBER

A workman controlling his own supply of oxygen while undergoing decompression in the hospital lock that is provided on all jobs of this kind for treating those who may become afflicted with "the bends" in consequence of "locking out" too fast upon leaving a tunnel.

PLAN AND PROFILE DRAWINGS

The plan shows where connections with existing express highways will be made at the two land terminals. In the profile drawings it can be noted how the rock line drops away abruptly a little south of Governors Island, a circumstance that necessitated using compressed-air shields in pushing the headings from the Brooklyn shore. To eliminate dealing with minus elevations, sea level was given an elevation of 300 feet.



Governors Island, where the ledge drops somewhat abruptly beneath glacial drift that forms the bottom of Buttermilk Channel. One exception to this promising outlook was discovered—an abrupt valley in the profile of the rock off Battery Park. This dipped into the projected line of the two tubes and extended below the crown or roof, and even the invert, indicating that a stretch would have to be advanced by use of the compressed-air method. As adopted, the line with its chosen gradients carries the roadways to a maximum depth of 115 feet below mean high water just abreast Governors Island, or 20 feet deeper than the maximum reached in the case of the Queens-Midtown subaqueous highway.

Originally, it was the intention to divide the work of tunnel driving into three contracts: Nos 5, 6, and 7. Contract No. 5 was to extend northward from the two construction shafts in Brooklyn for approximately 2800 feet, the advance to be in soft ground with the exception of some 300 feet of mixed face on entering the rock upon which Governors Island rests; No. 6, southward from the construction shaft in Battery Park, Manhattan, for a distance of about 2400 feet; and No. 7 was to cover the ventilation shaft in midstream and around 1700 feet of rock excavation north and south of that shaft in the Governors Island ledge. Between the specified northerly limit of Contract 5 and the southerly limit of Contract 7 was 400 feet of additional tunneling, and the contracts were to be written so that a part or all of it could be done under either. Similarly, there was 400 feet between the specified limits of Contracts 6 and 7.

Contract No. 5 was awarded to the George H. Flinn Corporation, which began work on the Brooklyn tubes June 23, 1941. The contract price, which included the 400 feet between Nos. 5 and 7, was $13,888,000. Contract No. 6 was let to Mason & Hanger Company, Inc., at a cost of $13,948,000 and included the 400 feet between Contracts 6 and 7 and that much of the Manhattan section first planned for Contract 7. Tunnel driving from the Battery Park construction shaft, which had been sunk by A. D'Angelo & Sons, Inc., was started the latter part of October, 1941.

Because of war restrictions, Contract No. 7 was not awarded until the first half of 1946, and under its terms no tunnel driving was involved. It was limited to the sinking of a shaft to a depth of about 30 feet below the bottom line of the tubes and to the construction of the substructure on which the ventilation building adjacent to Governors Island is to be erected. In consequence, excavating on the tunnel line under Contracts 5 and 6 was extended to a common meeting point 80 feet south from the center of the Governors Island ventilation shaft. Contract 7 was let to the Grow Construction Company at a price of $3,594,580.

The contractor for the Brooklyn tunnel sections started his operations at

CALKING LINING JOINT

Air tools quickly seal openings between segments of liner rings to prevent leakage of water that might later impair the appearance of the glazed tile with which the interior walls will be finished.



CAST-IRON LINING

At the top is a section of one of the tubes driven from Brooklyn, showing how the lining is made up of successive rings of bolted-together cast-iron segments. Athwart the tube is an intermediate bulkhead, with muck lock below, man lock at the end of the catwalk on the left, and emergency lock at the top. At the time the picture was taken the pressure was equalized on both sides and the muck-lock door was open. The other view shows how a liner ring is assembled. The erector arm of the shield is putting a segment in position for bolting to its neighbors.

the two construction shafts that had been sunk by Catapano Brothers under a separate contract. Sinking of those shafts had posed a problem because of the nearness of ground water to the street surface and because it was only a few feet below the tops of the tubes to be driven there. To lower it, to control its inflow, and to dry the ground, the contractor sank three dewatering wells capable, respectively, of receiving 500, 600, and 1000 gpm. Further, well points were used during the excavation of the shafts when the ground water had been lowered about 10 feet below the bottom line of the projected tunnels.

When the Flinn Corporation took over the shafts to begin driving the twin tubes, it had to deal with the same dewatering problem and, to do so, supplemented the previous equipment and dewatering wells by a Ranney dewatering installation. That plant consisted of a shaft 11 feet in inside diameter and having concrete walls 1 foot 2 inches thick. It was located 300 feet north of the construction shafts between the two tubes and sunk to a depth of about 63 feet below mean high water. From the bottom of the dewatering shaft radiated twelve horizontal strainer pipes spaced uniformly around the circumference at a point 57 feet below mean high water. These perforated pipes were forced into the ground from the shaft by jacking. They had an aggregate length of 1083 feet, and the longest extended 180 feet south of the shaft along the general line of the tunnel area. From there to a point 120 feet north of the shaft the drainage system lies 10 feet below the subgrade of the tubes.

The dewatering shaft was equipped with two pumps each of 2200 gpm. capacity. Pumping was started on December 19, 1941, and one day later the ground-water level had dropped as much as 29 feet. Continued pumping at that shaft and at the three construction-shaft wells at the rate of 4200 gpm. lowered it to an elevation below the subgrade of the tubes to a point more than 400 feet north of the construction shafts. This level was subsequently maintained.

Instead of having to drive his two shields from the construction shafts under air pressure, with inadequate depth and weight of ground cover to balance even moderate air pressure from beneath, lowering of the ground water permitted the contractor to start his tunneling operations in free air. The shields were in position and ready for their long burrowing northward toward Governors Island early in 1942. That in the east tunnel began moving the fourth week of February, and that in the west tube followed on March 11. Advance under free air was possible for a distance of 450 feet from the starting point and at a depth of 46 feet below mean high water. Then a concrete bulkhead and lock were built about 150 feet back from where the tunnel lining had been erected, and for a period of three months thereafter tunneling was done under reduced air pressure and with pumping. At that stage a second bulkhead was constructed.

On October 30, 1942, the War Production Board ordered suspension of work on the project because of the defense needs for steel and iron. At that time the west tube in Brooklyn had been driven 636 feet and the east shield had reached a point 1215.5 feet from its shaft—less than 200 feet from the river front. Both headings were closed with concrete bulkheads; the shields and other equipment were left in place; and the tunnels were kept dry by pumping until work was resumed in 1945.

Permission to go ahead was given in September of that year; but preparations had to be made before operations could

be taken up again. Advance of the west-tube shield was started about the end of November, while that in the east tube did not get underway until January 7, 1946. By the first of May the east-tunnel heading was about 1800 feet north from its construction shaft, and the workers were under air pressure of 32 psi. The west heading, which was approximately 270 feet behind, was under a working pressure of 25 psi. Operations were then proceeding beneath the river bottom where the formation consisted of sandy clay.

Pentration of this mass was a slow job, the daily advance being from 7 to 8 feet. The contractor had hoped when his shields were designed and built that he might be able to shove them "partially 'blind' through the stratified silt and clay under Buttermilk Channel"—that is, bodily displace some of that formation and admit only a moderate amount into the shields for transfer through a lock and thence up to the surface at the construction shaft. Instead, all muck had to be taken into each of the shields and disposed of laboriously.

Each shield weighs 400 tons and has an outside diameter of 31 feet 8 inches and an over-all length of 15 feet 10 inches from the cutting edge at the forward end back to the tail. Within the latter section is assembled and bolted to the previous ring the succeeding tunnel-lining unit, each of which has a width or longitudinal dimension of 32 inches. When the leading ring is bolted together and similarly secured to the one just behind it, the shield is shoved forward by 28 ten-inch-diameter hydraulic jacks arranged vertically in a circle just inside the shell of the shield.

The jacks, which are commonly operated at a pressure of 5000 psi., exert their thrust against the leading ring and, with that footing, push the shield into the ground. When the jacks are retracted, just enough space is left between them and the leading ring for the erection of the next liner ring, which is made up of fourteen segments—twelve "A" segments with radial joints and two "B" segments with flared ends to provide a space or keyway into which a tapered key unit fits with its wider end inside the ring. The several parts of the latter are lifted and held in place until bolted by a hydraulic erector arm, which is pivoted at the axis of the shield and can be swung around in a circle.

At each shove, a shield is advanced the width of a ring, and one completed ring remains within the tail and attached to the lining while the succeeding ring is being assembled and added to the lining. In this way only a restricted passageway remains between the shield and the leading ring through which compressed air from the heading can escape and mud or water flow inward. All or any number of the hydraulic jacks can be brought into action at each thrust and on any part of the ring, permitting the shield to be steered upward, downward, or to right or left. If there is any deviation from the prescribed course, it is checked by a surveyor before each advance and corrected at the succeeding shove. By this sytem of control the shield can be guided on a curved path, if so desired; and by suitable means, established as excavating proceeds, its course is continually checked backward to the surface where the line to be followed is fixed by visible survey marks or stations.

The tunnel driver of today can correct a shield's departure from the set course in another way—by the tapered ring, which is machined on one side and erected so that the next normal ring will correct the deviation whether up or down or right or left. And tapered rings can be deliberately used, like the segments in the elbow of a furnace smoke pipe, to give the tunnel a curving course in any direction. Also, when the concrete lining is being placed, the wall thickness top or



DETAILS OF SHIELD

At the top, welders are putting the final equipment on the rear end of a compressed-air shield. The hydraulic erector arm, which is pivoted at the center of the shield, is in horizontal position in the foreground. The numerous pipes which are visible lead to hydraulic jacks that perform various services. The other view shows the upper part of the forward end of a shield. In the foreground is a Utility air hoist that hauls and lifts materials used in connection with the operation of the shield.

BOLTING CREW

Here the bolts that hold the lining segments in place are being given their final tightening with long-handled wrenches. In the upper center may be seen the retracted plungers of two of the hydraulic jacks that push against the last ring, when bolted, to shove the shield forward a ring width.

bottom or at either side may be varied by purposely shifting the forms, thus keeping the axis of the tunnel straight so far as the observer can see.

On the front face of the bulkhead or structure to which the erector arm is secured are movable platforms that may be advanced or retracted by other hydraulic rams, and there are also heavy timber bulwarks that can be moved and forcefully held by the rams against caving wet ground while the latter is being undercut for removal so the shield can be pushed forward. The face is excavated a ring length from the top to somewhere below the spring line, and below that point the material is generally allowed to flow into the shield on a natural slope. The face is supported by breast boards about 2 inches thick, and they, in turn, are held in place by vertical timbers—called "soldiers"—that are braced by the shield platforms and face jacks.

The sand hogs work in pockets that are open toward the breasting where they are under air pressure sufficient to counterbalance the hydrostatic pressure at the given operating depth. Skill on the part of the tunnel driver keeps the air pressure at the face of his shield just slightly in excess of the outlying hydrostatic pressure, thus allowing for some escapage so that the air pressure will not be great enough to force its way outward and upward and cause a violent reaction in the form of an inundation at the front of the shield. Hydrostatic pressure is generally balanced at a level about 6 feet above the tunnel bottom. This produces a dry face above that level and a wet one below it. The excess air pressure required at the top of the face is counteracted by the weight of the overlying river bed which, when necessary, is augmented by depositing on it a partly impervious blanket of heavy clay.

While the shields in Brooklyn were advancing northward in free air through the drained area and then under air pressure below built-up Hamilton Avenue, grout and pea gravel were blown into the enveloping ground by compressed air after each shove to fill any space behind the shield and immediately outside the tunnel lining. That was done to check any settlement of the earth that might cause nearby buildings to subside.

During the first stage of tunnel driving in free air the contractor's forces erected three liner rings in 24 hours, and they accomplished about as much during the early period of their work under compressed air. But when confronted with mixed ground and rock they were able to place only one ring in 24 hours. The most difficult part of the job was encountered beneath the river upon first contacting the downward-slanting ledge of Manhattan schist on which Governors Island rests. There, most of the advance required continuous and troublesome breasting operations because the lower half of the face involved excavating rock and the upper half the river bed made up of a glacial deposit. Now that the entire face is in rock, tunneling is being carried forward by bottom headings that will undergo successive enlargement until full size is reached.

The George H. Flinn Corporation has used low-pressure air for its shield work and high-pressure air for pneumatic clay diggers, paving breakers, rock drills, and other air-operated equipment. Much pumping has been required to remove water seeping into the tunnel excavations and to operate the numerous hydraulic jacks on the two shields. The powerhouse in Brooklyn is ample to meet all pumping needs; and its seven large compressors have taken care of the varying air requirements.

The second installment of this article will appear in the October issue.



BROOKLYN COMPRESSOR PLANT

Two Ingersoll-Rand single-stage compressors in the George H. Flinn Corporation powerhouse. They are among five machines that furnished 29,300 cfm. of low-pressure air for use in balancing the hydrostatic pressure of the overlying silt and water in driving the shields forward. Also in the same plant are two I-R units, each of 2030 cfm. capacity, that supply high-pressure air for operating paving breakers, pneumatic tools, and other equipment needed for the work.

Princeton University's Unique New Library

C. H. Vivian

PRECEPTORIAL CONFERENCE

Informality is one of the features of Princeton's preceptorial method of instruction that was introduced by Woodrow Wilson when he was president of that institution. The group pictured has forsaken its regular meeting place in the professor's office for a nearby shady spot on the campus on a hot spring day.

PRINCETON UNIVERSITY, the fourth oldest institution of higher learning in the nation, is building a new library of unconventional type. Planned to implement the school's distinctive method of education that puts individual research above classroom instruction, the building will depart from the usual lines of construction and interior arrangement. More than 25 years of study and investigation preceded the actual drawing of the plans. As a result, the authorities believe they have devised a structure that will both answer current needs to greatest advantage and be readily adaptable to future changes in requirements as they may develop.

For some years a new library has been considered Princeton's most urgent need. This is because books, and more especially ready access to them, are of prime importance under the institution's scheme of instruction. The heart of this innovation is the preceptorial system that was inaugurated by Woodrow Wilson in 1905, three years after he became Princeton's president. His aim was to take the teacher off the platform and put him in informal contact with the students. In his own words, the plan "is meant to give the undergraduates their proper release from being schoolboys, to introduce them to the privileges of maturity and independence by putting them in the way of doing their own reading instead of 'getting up' lectures or 'lessons.' Their exercises with their preceptors are not to be recitatious, but conferences, in which, by means of any method of report or discussion that may prove serviceable and satisfactory, the preceptors may test, guide, and stimulate their reading. The governing idea is to be that they are getting up subjects—getting them up with the assistance of lecturers, libraries, and a body of preceptors who are their guides, philosophers, and friends."



OSTEOPLEURUS NEWARKI

During the excavation for the new library there were uncovered numerous specimens of small fossil fishes from rocks of the Triassic Age that were laid down probably 175 million years ago. Their scientific name is given above. Some of them are the finest of their type ever discovered and reveal details of anatomy never previously distinguishable. Knowing that Triassic rocks would be cut through, Princeton geologists watched the work for fossil vertebrates, although their searches in the case of similar rocks exposed in road cuts, quarries, and other excavations had been unavailing. This time, however, their vigil was rewarded. Most of the fossils were recovered in an area of 15x50 feet. After the first ones were found, the contractors co-operated with the scientists by digging carefully when working in the stratum that had yielded them. As a result, many more were unearthed in an unbroken condition. Most of them were in thin layers of hard shale, others in soft clay. The fossils range in length from 1 to 8 inches. The Osteopleuri had large heads, lacked bony vertebrae, and had a curious long third or middle lobe of the tail that extended beyond the end of the flat expanded part. Their lungs were calcified while they were alive and are preserved in some instances. The body was covered with oval-shaped scales from which numerous sharp spines projected. Princeton has presented specimens of the fossils to various museums and colleges in this country and abroad.

The introduction of the preceptorial system was the second step in the evolution of the Princeton plan of education. The first move was to organize the curriculum so that students might choose departments as they pleased rather than elect subjects. A definite relationship of the courses in each department was established at that time so that any combination the student might select would give him a fairly adequate knowledge of the entire field. At the same time, the number of courses was limited to the point where he would have to elect work in other departments to fill out his schedule.

Under the Wilson scheme, 50 preceptors were added to the faculty, and they soon became known as "those preceptor guys." However, this departure from traditional methods of imparting formal instruction worked well, and has continued to do so. It was designed to make a distinction between transferring information and transferring knowledge. In most schools a teacher passes out information and the student passes it back in recitations or written examinations. He may know the correct answer to a question and still not understand it or have a clear-cut idea of



GENERAL VIEWS

An architect's portrayal of the new building, above, shows the entrance facade, with a corner of the University Chapel at the right. Called the "Springboard of Princeton's postwar progress," it has been conceived as a place where a student "may pursue his education with books and faculty at his elbow." Although it will contain 3,400,000 cubic feet of space, its true size will not be apparent because its most massive part will be underground. Planned for maximum efficiency of service and economy of operation, the structure will house the largest open-stack library in existence. It will provide room for 1,800,000 volumes and seating accommodations for 1875 persons. Despite numerous departures from the traditional layout to implement Princeton's distinctive mode of preceptorial teaching, it will have a higher ratio of book space to total cubic content than any other large college or university library in America. In appreciation of gifts from the Firestone family totaling more than $1,100,000 the building has been named the Harvey S. Firestone Memorial Library. The cornerstone was laid (top-center) on June 16 of this year by Harvey S. Firestone, Jr., eldest of five brothers who are all Princeton alumni. A partial view of the steelwork for the superstructure is at the right. The new library will replace Chancellor Green and Pyne libraries, shown at the extreme right. The former was built in 1873 and the latter in 1897. They have been joined to form one structure.

its relationship to the subject. Knowledge, however, connotes understanding. Once acquired, it remains in the mind, whereas mere information may be very transient. It was the belief that knowledge could best be built up in students' minds by making the contact between them and their teachers close and informal. This is effected by dividing classes into relatively small groups.

A typical preceptorial conference numbers from six to ten men and is usually conducted at a regular class hour around a table in some university room or office. Sometimes, though, it may be held at night in the instructor's home. In either case, the atmosphere is informal. Reading has previously been assigned, and the assumption is that the students have done it and perhaps even thought about what they have read. The "precept" takes the form of an open discussion, with the preceptor acting as moderator. The general pattern is that of radio programs such as "Town Hall of the Air." Each student may have his say, or challenge the statements of others. Sometimes the argument becomes heated, and it is then that a conference generally produces the best results. The students quickly learn that the more they contribute, the more they receive in return. This encourages them to read and think, and that is the purpose of the teaching method. It has been called "untying a young man from the apron strings," and Wilson's idea was that it would lead students to "read and think for themselves along great lines of study, emancipated from school methods and stimulated to use their minds outside the class room."

Thus far the plan has been applied principally to upper-class and graduate-school studies. It is not possible to introduce it extensively in the engineering or science courses, where the lines of instruction must of necessity be rather rigid. It has, however, proved so successful in the other departments that it is proposed to intensify it where it is now used and to extend it to the freshman and sophomore years. A so-called "new plan" has been put forward by Dr. Harold Willis Dodds, who has been president of Princeton since 1933.

It is obvious from the foregoing that adequate library facilities are even more important at Princeton than in the average university. During the extensive preliminary planning period for the new structure, Doctor Dodds expressed the belief that it should be "a campus workshop where the three elements of the educational process—students, teachers, and books—can be brought in intimate association." And that, epitomized, has been the aim of the library's designers.

The Presbyterian educators who founded and nurtured Princeton in its early years had a keen sense of the importance of books. In the preface of the



school's first library catalogue, issued nearly 200 years ago, President Davies wrote: "A large and well assorted Collection of Books on the various branches of literature is the most ornamental and useful furniture of a college and the most proper and valuable fund with which it can be endowed."

We are not informed as to the size of this original "Collection of Books," but it has multiplied many times since then. Acquisitions were slow during the first century, and in Civil War days the library numbered only 25,000 volumes. This was a critical period in the school's history, as a large proportion of its students had been coming from the South and the enrollment dropped sharply. President James McCosh piloted it through the postwar recovery years, and during his tenure of office (1868-88) he increased the library to 65,000 volumes. By the time Woodrow Wilson doffed his academic robes in 1910 to become governor of New Jersey, it had mounted to 271,000 volumes. In 1936 there were 740,000, and now there are approximately 1,000,000, exclusive of unbound pamphlets and manuscripts. Some 200,000 of these are in departmental libraries and will stay there. The remaining 800,000 volumes will be removed to the new library.

In physical size, the building will be imposing. Three of its six floors will measure 350x225 feet, and all of them together will provide some 4½ acres of space. They will provide room for double the number of books the university now owns, but even so an eye has been cast toward possible future requirements by designing the structure so that it may readily be enlarged. Gauged by the monetary outlay it will represent, the building will be equally impressive. Prior to the actual beginning of construction, it was estimated that it could be erected for $3,500,000, but interim increases in prices of materials and labor have pushed the indicated cost up to $6,000,000. This is no mean sum, but virtually none of it will be spent on nonessential embellishments. On the contrary, President Dodds has emphasized from the start that the library is designed "to serve a virile educational purpose, and not, as has too often been the case in the history of college and university construction, to provide an architectural monument."

The task of raising the required money was undertaken by a committee headed by Paul Bedford of the class of 1897. Some $750,000 was contributed from the memorial funds of the various classes, and $500,000 was given by the Institution for Advanced Study, which makes its home in Princeton and whose staff includes many notables, among them Albert Einstein. The greatest single donation came from the family of the late Harvey S. Firestone, a pioneer in the development of rubber and an intimate of Thomas A. Edison. All five of his sons are Princeton graduates. They are: Harvey S., Jr., class of 1920 and now president of the Firestone Tire & Rubber Company; Russell A., class of 1924; Leonard K., class of 1931; Raymond C., class of 1933; and Roger S., class of 1935. Mrs. Firestone and her sons contributed $1,000,000 in 1945 and added $111,543 in February of this year. In appreciation of their generosity, the trustees of the university voted to name the new addition to the campus the Harvey S. Firestone Memorial Library.

The construction of the new library coincides with the opening of Princeton's third century of existence. It was chartered as the College of New Jersey on October 22, 1746, by John Hamilton, acting governor of the state. The first undergraduates reported to Rev. Jonathan Dickinson in Elizabeth, N. J., in May of 1747. Shortly thereafter activities were moved to Newark. When a permanent location elsewhere was sought, Princeton won out over New Brunswick primarily because Nathaniel FitzRandolph gave 4½ acres of land for a campus. (It now embraces 800 acres and some 80 buildings.) In 1754 the erection of Nassau Hall was begun there, and it was occupied in 1756. The name was changed to Princeton University in 1896. The bicentennial of the founding was observed throughout the period from September, 1946, to June of this year. At the concluding ceremony on June 17, President Harry S. Truman received an honorary degree. The day before, Harvey S. Firestone, Jr., had laid the cornerstone of the new library.

It is the interior arrangement of the library that has led to calling it "one of the world's unique educational structures." The basis of the scheme followed was advanced in 1932 by Prof. C. R. Morey, and its development into final



EXCAVATING FOR THE FOUNDATION

As subcontractor, George M. Brewster & Son removed 100,000 cubic yards of earth and rock from the 350x225-foot building site. The extreme depth to grade was 31 feet, with footings for piers extending 13 feet deeper. Rock was exposed at the surface on one side, and gradually sloped to a depth of several feet under the topsoil on the other side. Three portable compressors with a combined capacity of 1450 cfm. supplied air for drilling. A 6-inch delivery main was laid all around the site, with take-offs into the excavation area as required. Eight Ingersoll-Rand Type D wagon drills were used to drill the sandstone and shale rock. Several of them are illustrated at the top. After being blasted, the broken material was loaded into trucks by power shovels and hauled to disposal areas. The lower picture shows a bulldozer at work removing topsoil. In the background is a section of the University Chapel, one of the finest of Princeton's many attractive buildings.

form has involved study and planning on the part of innumerable individuals and committees drawn from the faculty, board of trustees, and alumni. The architects are O'Connor & Kilham of New York City. R. B. O'Connor of that firm holds a Princeton degree. His associate, Walter H. Kilham, Jr., spent parts of three years visiting libraries in this country and abroad during the period the plans were being formulated. Either together or individually, Messrs. O'Connor and Kilham have served as architects for libraries at Trinity College, Hartford, Conn.; Carroll College, Waukesha, Wis.; and an annex of the Morgan Library in New York.

The outstanding departure from tradition lies in the abandonment of any distinction between storage and non-storage space, and with it the elimination of all barriers between the books and their readers. The volumes that are in general use by the various departments of study will be housed in "open stacks," freely accessible and surrounded by offices, seminars, and reading rooms. Moreover, the interior arrangement will follow the modular plan of construction —which means that it will be made up of units of space uniform in size, illumination, and ventilation, and interchangeable as to function. The basic unit will measure approximately 18x25 feet, a size that is convenient for either book stacks or seminars. Two or more units may, by shifting readily removable partitions, be combined to form large conference rooms. In all cases, the ceiling height will remain at about 8½ feet which, it has been determined, permits of the most satisfactory illumination.

As an aid to individual study, there will be more than 500 cubicles or carrels for research workers. A student's carrel will be his own private study, located amid book stacks containing the volumes immediately pertaining to his endeavors. It will be furnished with a table, shelves, typewriter desk, adjustable lighting fixtures, and all other facilities for concentrated effort. There the occupant may keep the books that concern him at the moment. He can work undisturbed, and when he leaves for luncheon or for the day he can lock the enclosure, leaving books, notes, and partially finished reports without fear of their being molested during his absence.

Scattered throughout the book stacks will be "browsing alcoves," described as "oases of light, color, and attractive furnishings" to relieve the severity of the regimentation. Some of these will be no more than open spaces for a table and chairs for occasional reading. Others will be enclosed within partition walls permitting the display of prints, maps, and other graphic aids to study. In essence, this arrangement amounts to dividing a large reading room into smaller components, located at convenient intervals among the stacks. The rooms will seat from three to eight persons each. On the stack floors, also, will be two kinds of seminars: "talk rooms," and "work rooms." The former, as the name implies, will be primarily for graduate seminars under professorial guidance, with facilities for housing only such books as may be of immediate value. A work room, on the other hand, will be a miniature library of selected materials needed for carrying on a specific research.

Another novel feature will be the placing of the first three floors of the 6-story structure partially underground. Prior to the work of excavating, the site sloped downward in a generally northerly direction, with an extreme difference in elevation of 17 feet. By giving the

NASSAU HALL

Erected in 1756, ten years after the founding of Princeton University, this structure at one time housed all the functions of the college. The final stage of the Battle of Princeton was fought around it. New Jersey's first legislature convened in the building in 1776, and the Continental Congress met there in 1783.

ground north of the area a reverse slope —southward—it will normally be possible to obtain natural light from the north on all floors. Sufficient additional light will come in on the sides to serve about half the second floor and three quarters of the third floor.

The three lower floors will be approximately 350x225 feet in area and will be known as A, B, and C, in descending order. They will be the "stack" floors. Each will be large enough to house 500,000 books and, with the open stacks, carrels, and convertible units of space that have been mentioned, will be devoted primarily to the needs of specific departments of study. Floor A, for example, will be concerned principally with the Departments of Economics, Politics, and History. Along the full lengths of two walls and sections of the other two will be offices, seminars, and other study areas. All three departments will make use of a joint conference-lounge room.

The main entrance to the building will be at ground level and have a southern exposure. While in reality the fourth of the six floors it will be known as Floor 1, and the two above will be Floors 2 and 3. Placing the entrance approximately at the structure's midheight will minimize the distance that will have to be traveled to reach the various floors either by walking the stairways or riding the elevators. Aside from the functional advantages, there was an aesthetic reason for putting the roots of the edifice deep in the earth. The library is situated in the northeastern part of the campus and adjacent to the University Chapel, one of the most beautiful of the many attractive buildings that have earned Princeton the reputation of being among the sightliest academic plants in the country. If the huge library were to be reared entirely above ground it would dominate the area and detract from the chapel and other nearby structures. It would also virtually shut off the view of the chapel from Nassau Street, the principal business thoroughfare of corporate Princeton. These objections have been eliminated by putting most of the mass of the new building below the general ground level. The stories above ground will be much smaller than those underneath. The superstructure will be Gothic in architectural treatment so as to conform with that of the chapel and will be surmounted by a tower.

Upon entering the building the visitor will arrive almost immediately at the circulation desk, the nerve center of all library activity placed conveniently to serve him. There he will find the catalogue of all the volumes at his disposal; the Union Catalogue, which lists some three million titles of books in other libraries throughout the nation; and various other bibliographies of what has been published and where it can be found.

The physical equipment that will aid the staff in its work will be the most modern obtainable. It will include a pneumatic-tube system for dispatching call slips for books to the respective

JOSEPH HENRY HOUSE

To make way for the new library, this 110-year-old brick structure was moved 450 feet to its present location between Nassau Hall and Nassau Street, Princeton's main business thoroughfare. This marked the third time it has been shifted. It was built in 1837 as a residence for Professor Henry, who has been called "The father of the American electrical industry." Two years before Morse developed the commercial telegraph, Henry had set up a wire communication system in Albany, N. Y. Upon going to Princeton as professor of natural philosophy, he strung a wire between his office and home and used it to notify his wife whether he would be home for luncheon or if he desired some sent to him. By stringing a wire parallel to but 225 feet away from this first one he succeeded in passing a current between the two by induction, thus obtaining what scientists have recognized as the first "wireless effect." Among Henry's numerous inventions was the magnetic relay, which made long-distance wire communication possible. He declined to patent any of his discoveries. He left Princeton to become the first director of the Smithsonian Institution in Washington. In 1870, Henry House was transported, brick by brick, to a new site near Nassau Hall and on its old location rose Reunion Hall. The second move came in 1925 in order that the University Chapel might be built where the dwelling was then standing. Then it was shifted as a unit, as it was this time. The house is the traditional home of the dean of the college. Its last occupant was Christian Gauss, now dean emeritus. Its new tenant will be Dean Francis R. B. Godolphin.

floors where the volumes are stored. For the present it will operate only in a vertical line, but tubes have been placed in a tunnel underneath the bottom floor and reaching to the north wall in readiness for some future time when it may become necessary to extend the library limits.

The tube system will be put in by the Lamson Corporation of Syracuse, N.Y., which is a specialist in that field, and will function on the exhaust principle. Carrier capsules or cartridges will be 8¾ inches long and 4 inches in diameter, inside. When a carrier is discharged on any floor it will switch on a signal light in the various stack areas to notify attendants in the event the station is unmanned at the moment. Books will be carried up or down, as the case may be, by a vertical conveyor and will be automatically transferred on Floor 1 to a horizontal conveyor that will deliver them to the desk where they will be handed to those desiring them.

One of the first-floor rooms will be as close a reproduction as possible of the library of the College of New Jersey as it existed in the eighteenth century. It will contain the desk of Princeton's sixth president, John Witherspoon, together with several hundred of his books and others from the libraries of Aaron Burr, Jonathan Edwards, and other Princeton leaders. There will also be an Alumni Room, with books, prints, records, and trophies portraying the history of the institution. Special collections of rare books and manuscripts, the administrative offices, a reference reading room, a reserve-book room to supply general research needs, and newly received volumes will be on the same floor.

Floor 2 will be devoted mostly to special collections, including the Gest Oriental Library of 100,000 volumes, the Woodrow Wilson collection, and displays of coins and stamps. Floor 3, with book stacks, carrels, and seminars for the use of the Department of Classics, Oriental Languages, Philosophy, and Religion, will be similar in arrangement to the three lower floors but much smaller. A lounge room large enough to accommodate the entire faculty also will be located there.

The bottom three floors are being constructed of reinforced concrete. The superstructure will have a framework of structural steel and its outer walls will be faced with Foxcroft stone, which is being quarried near Swarthmore, Pa., and cut to the required dimensions at the building site. There will be no interior supporting walls, in keeping with the aim to set up no artificial barriers between the books and their users. Instead, there will be concrete columns to help carry the load and to house lighting conduits, piping, and ventilating ducts. Adequate circulation of fresh air to all parts of the library will be provided, but for the present only the sections for the rare books will be completely air conditioned.

The Turner Construction Company of New York is erecting this notable edifice on a cost-plus-fee basis. During the past 45 years that firm has put up 2000 buildings representing an aggregate cost of more than $700,000,000. Among them have been structures for Pennsylvania and Harvard universities, and numerous churches, libraries, and museums. Ground was broken on January 2, 1946. George M. Brewster & Son, of Bogota, N. J., did the excavating under a subcontract. This involved the removal of 100,000 cubic yards of material, one-third of it rock. At the deepest point, grade was 31 feet below the ground surface. Footings for supporting piers were carried 13 feet lower.

Construction is proceeding on schedule, and it is expected that the building will be ready for occupancy at the beginning of the regular academic term in September, 1948. Princeton has traditionally been a university of around 2600 students, but in common with other institutions its enrollment has been swelled far beyond that point by the influx of returned servicemen. When normal conditions are once more restored, it will probably be slightly larger than it was before the war. With the Harvey S. Firestone Library providing seating accommodations for 1875 persons, it should answer Princeton's needs for several generations to come.

Meanwhile, in the words of Librarian Julian P. Boyd, one of the leaders in the planning of the structure, it will seek to proclaim to the thousands of students who will enter it: "This is a place where books are gathered for your study and enjoyment. It is a building dedicated to the dignity and value of knowledge and of wisdom. It exists for these purposes alone. If the architectural ornaments are beautiful or if the technical paraphernalia of librarianship intrude themselves upon you, remember that they are present incidentally or through necessity. Their purpose is to house books and to make them conveniently accessible for your study and for the enlargement of the horizons of your mind."

PREPARING STONE

Exterior walls of the library will be of Foxcroft stone, a mica schist that is quarried at Broomall, Pa. Large pieces, weighing from 4 to 7 tons each, are shipped to a storage yard about 2 miles from the building site and are there reduced in size by drilling lines of holes (below) with Jackhamers and splitting with wedges. The resulting blocks, each of the approximate size needed, are trucked to a stone-cutting shed adjacent to the building where each is dressed to fit into its place in the structure. Most of the finishing is done with Dallett air hammers, and the foreman of the crew estimates that these tools save three-fourths of the time that would be required if the work were done by hand. The stonecutters are Italians, nearly all of whom learned their trade in their native land where stone is the predominating building material. The one shown at the right is using a toothed chisel to dress the face of a block of stone that will be exposed when it is put in its allotted space.



Keys to Everything

Allen S. Park



BALDPATE INN

At the left is a view of Baldpate Inn, a rustic summer hotel perched on the side of a mountain about 1000 feet higher than the village of Estes Park, principal settlement in Rocky Mountain National Park, Colo. Over its entrance hang seven keys on a ring (right). These and the name of the hostelry refer to the novel "Seven Keys to Baldpate" that was a best seller in 1915, the year the owners of the inn homesteaded the land it occupies.

AT BALDPATE INN, a summer hotel in Rocky Mountain National Park, Colo., there is an entire room full of keys. Of every kind and of every vintage, they cover the walls and hang from the ceiling. There are more than 10,000 of them, and the collection is growing continually. Most of the keys were either left or sent there by guests or visitors, and each one is tagged with the name of the donor and a description, long or short, some in prose and some in poetry.

It all started because the Inn's owners, Mr. and Mrs. Gordon Mace, homesteaded their land in 1915, the year in which Earl Derr Biggers wrote his best-selling novel *Seven Keys to Baldpate*. It was a mystery story revolving around an old house in a remote mountain setting. It was just such a locale as the Mace acres, so they called their place Baldpate, and when they built the hotel in 1917 they christened it Baldpate Inn. Over the driveway at the front door they hung a large replica of a bunch of seven keys, which was inspired by the fact that seven characters in Biggers' story turned up with keys although there was supposed to be only one in existence.

In 1922 the Maces conceived the idea of asking their guests to send them keys, and began furnishing them with tags to be used in forwarding them. Keys gradually started coming in, and soon there was a sizable nucleus of the present collection. By the time World War II was at its height they had 7720 keys, and a separate room just off the lobby of the inn had long before been set aside for displaying them. All had been acquired without any special publicity. Then one of the motion-picture newsreels based a short on the collection. That was shown to our servicemen and women all over the world and precipitated a veritable deluge of keys. They began to arrive from here, there, and everywhere, swelling the number to more than 10,000.

There are keys of many sizes and materials. The largest is of wood and was sent by two young men of St. Joseph, Mo. The smallest is scarcely ½ inch long. There are keys of most of the known metals, including one of Colorado native metals that was given by the Colorado School of Mines. A retired railroader presented one made of metal from the bell of an old Santa Fe Railroad locomotive. There is an ivory key that was used in early Egypt, and one from a neon-sign man that is fashioned from glass. Among the numerous wooden keys is one whittled from a timberline tree on Long's Peak, the 14,255-foot eminence that graces the skyline west of the inn.

Many of the keys were donated by well-known people. Gipsy Smith, the revivalist, sent one from the Teikoku Hotel in Tokyo. The late Clarence Darrow, leading criminal lawyer, was one of the first guests to offer a key. Charles E. Mace, brother of the inn's host and official photographer for Gen. John J. Pershing during World War I, contributed keys from significant battle points in that conflict. Mr. Biggers left a key, tagged with the following inscription in his own handwriting: "This is the original key to Baldpate—all the rest are imitations. The old man gave it to me the day before he died." The words allude to the plot of his story.

The Biggers novel was dramatized by George M. Cohan, who played the leading role long and successfully. When he

THE KEY ROOM

Two views of the room that contains 10,000 keys of every type and description and from the ends of the earth. The lower picture shows the fireplace, with a large keystone contributed by one of the guests.

appeared in Chicago on November 21, 1938 (in another play), Mayor Edward Kelly gave him an engraved key to the city. That is now in the Mace collection. "Seven Keys to Baldpate" was the first talking motion picture in which Richard Dix appeared, and the key he used was donated by him to the inn. Jack Benny and Mary Livingston were guest artists at a radio version of the play and they, too, added keys.

In the collection are hotel-room keys from the world over, including the Castle Harbour in Bermuda, the Ritz in Paris, the Grand in Copenhagen, the old Waldorf-Astoria in New York City, and the former Old English Hotel built in nearby Estes Park by Lord Dunraven long before the area was a national park. James O. Stevic, Denver postmaster, sent a hotel-room key with a history. A man returned it to a Denver hostelry with a note saying he had carried it off eighteen years before. There was ten cents postage due, and after it was determined that the key wouldn't fit any of the locks in the building, the hotel proprietor refused to pay the charges. When the mail carrier brought it back to the post office, Mr. Stevic dug into his pocket for a dime and forwarded the key to Baldpate.

Many of the keys concern famous places, objects, or events. There is even one from the United States Capitol in Washington, D. C., donated by W. R. Eaton, former congressman from Colorado. He obtained it from David Lynn, architect of the Capitol, who had to get an official order authorizing him to release it. There is a key to the Royal Chapel in Westminster Abbey, and one that opens a side-gate entrance to Buckingham Palace. Also in the collection is the key to the fire-alarm box in Chicago that was used to turn in the alarm of the disastrous 1871 fire. The box was at DeKoven and Desplaines streets.

Another key would admit one to the house in Bardstown, Ky., where Stephen Collins Foster wrote "My Old Kentucky Home" and other immortal songs. A

key that dates from 900 A.D. fits a lock in the crypt where Ibrahim Pasha is entombed with the caliphs and where many members of the royal family of Egypt are buried. Believed to be the oldest of all is a hand-made key obtained from Ahmed el Malusi of Tetuan, ancient capital of Spanish Morocco. A key to the east gate of the largest mohammedan mosque, which faces the Great Pyramid of Gizeh, is 500 years old. There are keys to Nebraska's former and present capitol buildings, and one to Mozart's wine cellar. Upon seeing the latter, a woman visitor to the inn is reputed to have exclaimed: "Oh, was he here?" On a par with this remark was one by a lady who, upon being told that most of the keys had been left by guests, responded: "My, aren't people forgetful?"

Together with other keys having to do with unlawful acts, Baldpate Inn has one to the Southern Bank of Kentucky, the first bank robbed by Frank and Jessie James. A surprisingly large number of people have contributed jail keys, but the Maces never ask guests how they came by them. There are keys that give entry to many college buildings, including one for the door of the first building of the School of Mines at Columbia University, as well as emblem "keys" such as Phi Beta Kappa and Kappa Kappa Gamma worn by members of college societies and fraternities.

Numerous keys pertain to the field of transportation. Among ships' keys is one from the German submarine *Deutschland*, which made two trips through the British blockade during World War I, putting in at Atlantic Coast ports to obtain vitally needed materials before we entered the conflict. There is a key that was cast from metal that was carried as ballast by the balloon *Explorer I* when it reached a height of 57,000 feet in 1934. It took off at Rapid City, S. Dak., and landed in a cornfield near Loomis, Neb. The Burlington Lines presented a key of stainless steel from the original "Burlington Zephyr," which initiated diesel-locomotive streamlined passenger service in the nation. Another is from the Union Pacific's "City of Denver" streamliner. There is also a key from the first United Air Lines Mainliner plane routed through Denver on May 15, 1937. Paul E. Johnson, an airmail pilot, dropped a key by a miniature parachute while flying over the inn. Cunard-White Star line officials sent a key from the liner *Queen Mary* following her initial visit to New York on June 1, 1936.

Keys other than door keys are in the collection. Watch and clock keys, some old and some new, are numerous, and included are keys to cash registers. A printer gave a quoin key used to lock forms for presses, and a stenographer contributed a shift key from a typewriter. There are cotter keys, flywheel keys, keys of the kind that open sardine cans and soldiers' K rations, and also a turnkey, an instrument by which teeth were pulled a century ago. Among the piano keys are seven from the first instrument to cross the plains to Denver in a covered wagon.

Many persons have donated symbolic keys such as the "key to happiness"—a ruler of gold engraved with the Golden Rule. Someone sent an old ox yoke that had been used by pioneer travelers and came placarded "The Key to the West." There are various artistic representations of keys, including a plate decorated with a design of seven keys. It was given by a former governor of New Mexico and his wife, Mr. and Mrs. Sotero Montoya. Other donors have played upon words such as whiskey, monkey, donkey, turkey, and darkey to bring their contributions into the category of keys.

Many objects have been converted into representations of keys in order that they might have places in the collection. Among these are two keys made from rock-drill steel that had seen service on construction jobs in the region where the inn is located. One piece had been employed for drilling blast holes during the building of the South St. Vrain Highway in 1936. This scenic route enters Rocky Mountain National Park from the south and passes close to the hostelry. The contractor, Platt Rogers of Denver, presented the key to the Maces.

The other key was formed from the drill rod that completed the final portion of the final hole for the last blast in the Alva B. Adams Tunnel, which penetrates the main range of the Rocky Mountains. This 13.1-mile bore—the longest ever driven from only two headings, will carry western-slope water through the mountains to irrigate farm lands on the eastern side. The two drilling crews met on June 10, 1944, at a point 44,994 feet in from the east portal, where the final round was put in by S.S. Magoffin Company men, Denver contractor on the east end. James R. Pierce, Magoffin blacksmith, converted the steel into a key. On the end of it is screwed one of the Ingersoll-Rand Jackbits that was used in drilling the final round. The key was added to the collection by Frank Purvis, superintendent for the Magoffin forces on the job.

There is a special reason why these two drill-steel keys are of great sentimental interest to Mr. Mace. Prior to homesteading the land where the inn stands he worked for sixteen years for the J. George Leyner Engineering Works near Denver. It was there that Leyner, about 1896, developed hollow drill steel. By thus providing a means of sending water and compressed air through the steel to clear away rock cuttings at the bottom of a hole he made it possible for the first time to utilize hammer-type rock drills, of which he was a pioneer manufacturer. As a result, hammer drills came into universal use and the speed of drilling rock was greatly increased. The steels of which the two keys are made is of this same hollow type that is still known in many mining areas as "Leyner steel." By the same token, many old-time miners continue to call hammer-type drifter drills "Water Leyners."



DRILL-STEEL KEYS

These representations of keys were made from pieces of hollow rock-drill steel. The lower one was used during the construction of the scenic highway that passes near the inn. The other one helped drill the last hole of the final round blasted in the Alva B. Adams Tunnel through the Continental Divide. The east portal of that 13.1-mile bore is about 3 miles from Baldpate Inn.

Inserting wiring by hand is one of the most expensive operations in manufacturing radio sets. To overcome this, the Promenette Radio & Television Corporation of Buffalo, N.Y., sprays it in place with air. A mask with openings corresponding to the desired circuits is first laid on the sets plastic chassis into which grooves for the wires are thus sandblasted. Molten copper with a zinc or aluminum primer is then applied through another mask with a metallizing gun, using pressure of 60 psi. The picture (right) shows the metallizing gun and mask.

WIDE WORLD PHOTO

It is claimed that an automobile can be washed, polished, and dried in one minute by an apparatus developed by the Minit-Man Auto Wash Company of Detroit, Mich. Washing is done by revolving brushes and water that contact all car surfaces. Endless floor belts spin the wheels to assist in cleaning them. From the washing station the auto is towed to the drier (above) where air is blown on it at high speed through ducts, removing the water and drying the surfaces in a few seconds. Air is supplied by the motor-driven blower shown at the upper-right.



Right—For use in connection with its high-speed band saws widely employed for cutting nonferrous metals and plastic materials, the DoAll Company of Minneapolis, Minn., has introduced a spray lubricator that operates on air pressure from plant distribution lines. The spray head straddles the saw blade and directs a mist of lubricant-coolant against the teeth from each side, forcing it into the cut. The liquid is drawn from a 1-gallon container mounted on the side of the machine and is metered as desired by means of a valve and sight glass. So little fluid is applied by this spray method (1½ quarts per hour) that no mess is created on the worktable or the material being cut.

Left—The man at the right is controlling a British-made tractor plow by radio. He transmits impulses to sensitive electric relays which, in turn, actuate compressed-air servomotors that operate the controls. The tractor can be made to go straight or to turn right or left. At the end of a furrow the plow can be raised. Compressed air under high pressure is stored in the flask mounted on top of the machine. Because it is so light, this unit is said to operate all day on the fuel a conventional tractor consumes in one hour.

ACME PHOTO

The young lady shown below is about to pick up twelve cans of vegetables that have just been delivered from a closing machine. A rubber cup, to which vacuum is applied by means of the hose, fits on the top of each can. A rope (behind the hose) passes over a pulley overhead and is counterweighted to balance the 20-pound load and make it easy to transfer it to retort crates. There is a trigger release on the handle. Formerly moved by hand, four cans at a time, this was a wearing task. Vacuum of 16-18 inches is induced by a pump, the requirement being about 6 cfm.

ENGLER VACUUM LIFTER, INC.





Compressed Air at Work

Editorials

BROOKLYN-BATTERY TUNNEL

THE insular character of the Borough of Manhattan, one of the five geographical components of New York City, has reacted both to its benefit and detriment. It has given it an extensive shoreline without which it could never have attained its preëminent position among world ports. Inasmuch as most of its early commerce was water-borne, its detachment from the mainland was then a decided advantage. The spacious harbor, the Hudson River, and then the barge canal to the northward and westward served to move goods to and from the island at low cost and made it the center of our import and export trade. Such intercourse as was necessary with neighboring land areas was carried on by aid of rowboats and sailing craft.

As the city grew beyond the confines of Manhattan, and settlements were established on Long Island, Staten Island, and in New Jersey, steam-driven ferryboats appeared to meet transportation needs. When they no longer sufficed, the Roeblings electrified the world with their daring engineering achievement of spanning the East River with the Brooklyn Bridge. It was opened to the awed populace in 1883 and paved the way for the Williamsburg, Manhattan, and Queensboro spans. The broader Hudson River, however, had no such crossing until O. H. Amman, chief engineer of the Port of New York Authority, executed the George Washington Bridge in 1931.

Meanwhile, intrepid engineers had burrowed tunnels underneath some of the waterways. As early as 1874, DeWitt C. Haskin had attempted to drive tubes under the Hudson, but it was not until 1908 that the tremendous financial and technical obstacles were overcome through the combined business acumen of W. G. McAdoo and engineering skill of Jacobs and Davies. Mr. Jacobs, who had come here from England, had previously demonstrated the effectiveness of the compressed-air-shield method of tunneling by excavating a small bore underneath the East River to carry gas. The McAdoo twin tubes and the Pennsylvania Railroad tunnels that were started in 1900 were for rail transportation. The construction of subways also was begun in 1900. In the years that followed, numerous tubes were driven underwater to provide connections with the boroughs of Brooklyn, Queens, and The Bronx.

When the automobile arrived on the scene, new problems appeared. Many of Manhattan's streets had to be revamped and express highways built to accelerate traffic. More bridges and subaqueous tunnels were needed to connect with through routes. The Triborough, Whitestone, Goethals, and other spans were erected. In 1920 work was launched by Clifford M. Holland on the first vehicular tubes between New York and New Jersey. He didn't live to see their completion in 1927, but they were named for him in recognition of his devotion to the project. Another Hudson vehicular tunnel—the Lincoln—came next, and then the Queens-Midtown Tunnel. Even all these facilities, plus the numerous ferries that ply the waters, have failed to provide free flow of traffic for New York's million automobiles and the sizeable number of visiting cars. That is why sand hogs and hard-rock tunnelers are again burrowing, and this time under the harbor waters between Manhattan and Brooklyn.

Subaqueous boring is an old story to New York construction men, but it is still ticklish business that must be thoroughly planned and meticulously executed. The Brooklyn-Battery Tunnel encountered geological problems that called for even more care than usual. At one end it is in rock that is none too thick or stable overhead for comfort, while at the other end it pierces silt and mud. Knitting the oppositely advancing sections together with precision and security was a man-size job that has now fortunately passed through the critical stage. Credit for skillful and efficient performance of hazardous work is due all those who have had a part in conceiving and carrying out this momentous engineering undertaking.

BIRTHDAY OF U. S. IRRIGATION

MODERN irrigation in the United States is an even 100 years old. The Mormon pioneers initiated it in July, 1847, when they dug a ditch near Great Salt Lake to divert water from a creek to their newly planted potato patch. Since then irrigation has become a vital instrument in the development of lands comprising one-third the area of the country and one-fifth of its population.

To produce crops successfully it is necessary to supply the soil with from 20 to 25 inches of water, and it must be well distributed throughout the growing season. Sixteen of our western states cover 740 million acres having an average annual precipitation of less than 20 inches. Twenty percent of this land receives less than 10 inches of water in an average year. The deficit must be made up by impounding and distributing surplus run-off water. Thus far, only 22 million acres have been irrigated—a mere 3 percent of the total—and half of those acres are still inadequately watered.

Even so, approximately 40 percent of all the water that runs off in surface streams is now being utilized. In other words, if all the available stream water were conserved and distributed, there would be only enough to meet the shortage in the case of the 22 million acres now being irrigated and to supply an adequate quantity for an additional 22 million acres. This means that only about 6 percent of the land can ever be brought to full crop production.

In the beginning, settlers merely diverted water directly from streams to low-lying lands. As higher lands were brought under cultivation, it became necessary to tap the waters farther upstream and to build longer canals. To insure a supply during the late growing season, when stream flows diminished, storage reservoirs had to be constructed. These were filled during the spring floods and drawn down later as needed. As more extensive works were required costs went up, and there came a time around the turn of the century when farmers, working singly or in groups, had about reached the limit of their ability to finance such projects. It was apparent that government help would have to be provided, and this was made possible by the creation, in 1902, of the U. S. Bureau of Reclamation upon the recommendation of President Theodore Roosevelt. Since then, bureau-built facilities have supplied water for growing five billion dollars worth of crops—a sum more than five times the cost of the construction projects involved.

Currently, the bureau has a long-range program which contemplates the expenditure of 1½ billion dollars to harness western rivers for irrigating water, to produce power, to control floods, and for other incidental benefits such as recreation facilities and the conservation of wild life. The schedule for the 1948 fiscal year calls for 195 million dollars worth of work, but it will have to be curtailed unless Congress appropriates an additional 36 millions.

Reclamation is not boondoggling. From its inception, the bureau has been run on a businesslike basis. Farmers sign contracts in advance of construction that provide for repayment of money spent for irrigation. Where power-generation features are included, the balance of the cost is returned to the Government through the sale of electricity. Because virtually all our beet sugar and an appreciable proportion of our meat and many other food products come from these western irrigated lands, all of us are affected by the bureau's activities.

This and That

"Steam" from Dry Ice

To obtain the effect of swirling clouds of steam desired for a series of window displays, Lord & Taylor, one of New York City's fine department stores, made use of dry ice and compressed air. Two hundred pounds of the solidified carbon dioxide was placed on a sheet of glass each morning, and the white vapor given off by it was blown about by compressed air at 2 pounds pressure directed against the block from opposite directions by means of two hose lines.

★ ★ ★

Shot Peening Award

For originating the technique of shot peening to harden and increase the durability of metal surfaces, F. P. Zimmerli, of Detroit, Mich., will be given the 1947 Albert Sauveur Award by the American Society of Metals. The method is widely used in hardening metal parts of machinery ranging from aircraft and automotive engines to turbogenerators. It was described in our January, 1947, issue. About twenty years ago Mr. Zimmerli conceived the idea that shot peening would increase the fatigue life of springs, and the company with which he was associated first applied it for that purpose in 1929. The citation states that, "In many cases, the application of the knowledge we now have on the subject of surface stress is dependent on the extensions of the original work, but is nonetheless based on Zimmerli's early investigations." Shot peening is done by propelling steel pellets against a metal surface with a stream of compressed air, the technique being similar to that of sand or shot blasting. Mr. Zimmerli is chief engineer of the Barnes-Gibson-Raymond Division of the Associated Spring Corporation, Detroit. He is a graduate of the University of Michigan, where he formerly taught.

★ ★ ★

Lincoln Invention Revealed

An old and scarce U. S. Patent Office publication owned by the William L. Clements Library at the University of Michigan reveals that Abraham Lincoln was granted a patent on May 22, 1849, for an invention designed to ease river boats over shoals and sand bars. As described in the patent application written by Lincoln's law partner, William H. Herndon, the gist of the scheme was "to attach a kind of bellows on each side of the hull of a craft just below the water line; and by an odd system of ropes and pulleys, whenever the keel grated on the sand, these bellows were to be filled with air; and thus buoyed up, the vessel was expected to float clear." It is said that Lincoln conceived the idea after being a passenger on a Great Lakes boat that assisted another vessel in getting off a sand bar. Being an expert whittler, the inventor fashioned a wooden model of his innovation with a jacknife. The model is still in the Patent Office.

★ ★ ★

Small Horses Needed

All riding horses for police service in the British West Indies since 1927 have been shipped there from Canada. Small animals weighing from 900 to 1100 pounds are selected for the purpose because they eat less than larger ones. This is important in view of current prices in the islands of eight cents a pound for oats and six cents for hay. Recently three mounts were sent to the Commissioner of Police for Barbados and twelve to the head of the force in Trinidad. The horses are purchased by the Dominion Department of Agriculture from breeding stations that it has helped to maintain in the Province of Ontario for the past 25 years.

"There he noticed it was wet, so he ran hell bent down the road."

★ ★ ★

Famous Rand Mine Closing

Rising mining costs have reduced profits of all South African gold mines and even forced some of them to close. The latest victim of these economic conditions is Van Ryn Gold Mines Estate, which curtailed operations on July 1 and announced its intention to close down entirely within a few weeks. The Van Ryn began crushing ore in 1892, and the present company dates back to June 22, 1894. Up to June 30, 1946, a period of 52 years, it had produced 22,482,607 tons of ore with a yield of 4,860,462 ounces of gold, valued at 25,013,632 pounds sterling. Dividends of 4,082,000 pounds sterling were paid, equivalent to 933 percent on the invested capital. In June, 1947, the mine was employing 370 Europeans and 3161 Natives. For some years past, the ore has averaged less than $4 in gold per ton, and working costs have gradually increased until no margin of profit is possible.

★ ★ ★

Better Phone Wire

An advertisement of the Bell Telephone Company of Nevada in a mining paper in that state tells of a new steel wire so strong that the number of poles needed on rural telephone lines can be cut nearly in half. With the wire previously available, poles were generally 250 feet apart, whereas the new product permits placing them on 400-foot centers and more. This will obviously make scarce materials go farther and at the same time speed up construction. The improved wire, which is especially applicable to rural service, was developed by the Bell Laboratories. The company also announces that rural subscribers may expect fewer people on their lines and the gradual replacement of crank-type phones with modern instruments like those common in urban communities for some years.

★ ★ ★

Flood Proof Motors

General Electric Company has supplied Crown Zellerbach Company's paper mill at West Linn, Oreg., with six 2300-hp. synchronous motors that are protected against complete submersion. They will drive wood-pulp grinders that are normally in the dry but that may at times be covered with water, since the mill is located on the bank of the Willamette River, a stream that sometimes rises 40 feet during the spring thaw. On those occasions the mill has to suspend operations. The motors are completely inclosed by reinforced-steel end plates with ventilating holes which will be open while the motors are running but will be sealed during flood periods. As a further precaution against damage, compressed air will be blown into the motor frame through a pipe connected at the top of each casing. This will serve to maintain pressure within and exclude the water.

Machine Removes Scale from Welded Axle Housings

AS A RESULT of processes that were developed during the war, an automobile manufacturer has been able to save materials and machining costs by substituting a stamped and welded tube for the conventional cast and machined rear axle housing. This change, however, was not effected without difficulties. When the halves were seam-welded together a scale formed on the inside of the tube and it was feared that it would eventually flake off and mix with the differential-gear lubricant to form an abrasive that would harm the gear. When high-pressure sprays were found to be ineffective, the concern turned to the Howard Engineering & Manufacturing Company for a mechanical method of removal.

The machine that was developed works automatically and is equipped not only to loosen the scale but to wash the inner and outer surfaces. The work is carried through it on a conveyor belt with an indexing arrangement that stops each housing as it arrives at the first station. There a steel brush is pushed into it by a pneumatic cylinder and, as it revolves, a cleaning solution is sprayed in and around the wires as well as the tube's exterior, cleansing the walls and flushing away the scale and other foreign matter. After a predetermined interval the air cylinder retracts the brush into a cabinet, where it remains when not in use. Then the conveyor moves to the next stop where the housing is dried inside and out with blasts of hot air.

During the successive operations the work is held in correct position. Movement of the brush, which is connected by a shaft to the pneumatic cylinder, is regulated by valves which are synchronized to function when the indexing mechanism goes into action. Metering valves in the air-supply line permit close control of the brush travel, and air ranging in pressure from 60 to 90 psi. may be used to actuate the cylinder. Four machines of the type described have been installed and are said to have solved the problem.



INTERNATIONAL NEWS PHOTO

NEW ARMY AIR DREADNOUGHT

This 139-ton Consolidated-Vultee B-36 plane can carry an atom bomb to any inhabited area on earth and return to its base without refueling. Its maximum load capacity for short trips is 36 tons, enabling it to take along its own fighter escort planes and launch them when near the objective. The craft is pressurized for the comfort of its 12-man crew during stratospheric flight. Following tests of the initial model, the Army announced that it had ordered a "substantial quantity" of the new bombers. The lower view shows a crew member on his back pulling himself through an 85-foot-long pressurized magnesium-walled tunnel that connects the fore and aft compartments.

Sound Waves Inspect Metal

DURING the war, German technicians developed a supersonic method of locating bubbles in sheet metal too minute for detection by X-ray or magnetic processes. A report on the device prepared by Dr. G. J. Thiessen, a member of the National Research Council at Ottawa, Canada, states that the method tests sheet metal for imperfections by comparing the energy of supersonic vibrations before and after passage through the metal. Anything greater than the normal drop in transmission indicates the presence of a flaw. Experiments have shown that a bubble only one-hundred thousandth of a millimeter in diameter can cause a hundredfold drop in energy. Slag- or rust-filled bubbles do not cause a drop of like magnitude but, even so, are readily discovered.

The supersonic vibrations are generated by a 15-watt quartz-crystal sender that operates at 1000 kilocycles and "wobbles" the frequency 100 cycles per second to prevent standing waves in the metal undergoing test as well as between the sender and receiver. The vibrations are transmitted by a metal block to a narrow chamber of running water which, in turn, passes them on by making contact with one edge of the test metal. A similar arrangement picks up the vibrations at the other edge and forwards them to the receiver. The sending and receiving units are attached to opposite ends of a long pair of tongs that straddle the sheet, move along its edges, and are kept in contact therewith by hand pressure or by springs in the tong handles.

Full details about this and other methods of inspecting metals are contained in a report, entitled *The Non-Destructive Testing of Materials and X-Ray Protection Methods*, which can be obtained in photostat, microfilm ($1), or mimeographed form (25 cents) from the Office of Technical Services, Department of Commerce, Washington 25, D. C.

COMPRESSED AIR HANDBOOK

New Books

Reference Volume on Pneumatic Equipment and Practices for Both the Operating Man and the Layman

DESPITE the extensive and varied uses of compressed air, relatively little literature has been available to assist engineers and others in the installation and operation of air compressors and air-powered tools and equipment. The need for such assistance is great, and to meet it partially Compressed Air and Gas Institute has published *Compressed Air Handbook*.

The volume is designed to serve as a source of reference data for technical and engineering purposes and to inform both the student and the layman of the adaptability, flexibility, and usefulness of compressed-air power. In addition to considerable data of recent origin that has not been available previously in a single book, it contains in revised and improved form all the reference material formerly published as *Trade Standards*.

Nineteen of the nation's leading manufacturers of compressors, air-operated tools, and allied equipment constitute the membership of the Compressed Air and Gas Institute, and they have pooled their experiences and knowledge in the new handbook, which has been in course of preparation for two years. An idea of its contents may be gained from the following chapter headings: Typical Applications of Compressed Air, Representative Types of Compressor Installations, Portable Air-Operated Tools and Rock Drills, Engineering the Compressor Installation for Maximum Efficiency, and Compressed Air Engineering Data and Test Procedure.

Compressed Air Handbook contains four hundred 6x9-inch pages, with 247 illustrations, including photographic reproductions and diagrams. It is bound in stiff-backed simulated leather, with gold-embossed lettering. Available from Compressed Air and Gas Institute, 90 West Street, New York 4, N.Y. Price $3 in the United States; $3.50 elsewhere.

ILLUSTRATIONS FROM "COMPRESSED AIR HANDBOOK"

The actual pressure available at a pneumatic tool can be learned, as shown above. A hypodermic needle, to which a gauge is attached, is inserted into the air hose close to the tool and the reading taken. When the needle is withdrawn, the hole seals itself.

The controlled breathing apparatus shown above in the hands of a nurse has saved many lives in hospitals. Intermittent pulsations of compressed air simulate the natural action of breathing when a patient needs this assistance while on the operating table.

Meat loaves baked in a packing house were formerly removed from their pans by pounding the latter on a table. This took time and labor and was hard on the pans. A jet of compressed air applied around the edges of a loaf now quickly loosens and ejects it.

A Mining Romance

JOSEPH R. LINNEY spent the early part of his adult life in the anthracite coal-mining district around Scranton, Pa., and rose to an executive position with one of the large operating companies. More than a quarter-century ago the same concern assigned him to direct the nation's largest magnetite iron mines in the Adirondack Mountains of northern New York. These properties, some located near Port Henry and others near Plattsburg, have been worked since 1938 by the Republic Steel Corporation. Mr. Linney served as general manager of the mines until a year or two ago. His two sons Robert and William, well known in the sports world as makers and breakers of bobsledding records, are now in charge of them.

These biographical notes are set down here because there is much similarity between the career of Joe Linney and that of Jim Lane, the hero of a novel with which Mr. Linney has busied himself since retiring from mining. In his introduction the author states that the story is a combination of fiction and fact, but admits that the inspiration for writing it came out of his own experience in the mining field. In any event, the novel opens with Lane, a young mining engineer, being transferred from the Pennsylvania anthracite mines to the New York iron mines, and then traces his steps in rehabilitating the run-down properties and instituting new milling methods to produce a concentrate of the required iron content for commercial steel-plant utilization. He succeeds with the aid of Betty Dale, a community nurse, and their romance forms one of the main threads of the tale.

Tales of the Rideau Lakes

AUTHOR, FISH, AND LOCK

British soldiers, working under the Royal Engineers, spent five years and $5,000,000 building 47 locks and 24 dams and digging 6 miles of canals to enlarge the Rideau Lakes and to connect them into a 126-mile navigable waterway. Little Rideau Lake is the high point, from which there is a 277-foot descent to Ottawa and one of 161 feet to Kingston. One dam, at Jones' Falls, is 400 feet long, 80 feet high, and 300 feet thick at the base. The masonry in the dams and lock walls consists of accurately cut limestone blocks, laid without the aid of machinery in tiers, that are in as good condition today as when they were put there. The original massive lock gates were of oak. Now they are of Douglas fir, and they are renewed on an average every ten years. All locks are 124 feet long, 24 feet wide, and 6 to 8 feet deep. One of them is shown at the right filling with water. At the top Clint Fleming is contemplating a large-mouth bass.

A MAN who has devoted 45 years to guiding fishermen knows a lot about both fishing and human nature. That is probably the reason why a new book, *When the Fish Are Rising*, makes good reading. Its author, Clint Fleming, has spent almost half a century with fish and people, and the fourteen stories that make up his maiden effort at writing cover many types of both. Consequently, you don't have to be a fisherman to enjoy it.

Fleming does his guiding in the Rideau Lakes district of Canada, and his introductory chapter on its historical background will interest construction men and engineers. The lakes were canalized by order of the Duke of Wellington following the War of 1812. Fearing further trouble between Canada and the United States, he built a waterway from Ottawa to Kingston over which troops and supplies could be moved as an alternate route to the Yankee-fortified St. Lawrence River. The canal, of whose 126-mile length only 6 miles had to be dug, never had to be used for military purposes, but it did provide one of the finest fishing grounds in North America. It is now largely patronized by vacationists from the United States.

Through the pages of the book pass expert anglers with their expensive outfits, native Canucks who catch their share of fish with heavy poles cut in the bush, and tired businessmen who often find the tonic of the outdoors better for their real or imaginary ills than medicine. The finny characters include pike, walleye, muskellunge, lake trout, and especially large- and small-mouth bass. From a lifetime of experience, the author writes of their habits, peculiarities, obstinacies, and of the best lures and techniques for taking them.

Woven into the stories are word pictures of the natural beauty of the Rideaus, the author's fishing tips, theories on conservation, and philosophy of life. The duties of a guide are also set forth. In his day, Fleming estimates, he has prepared 5000 shore dinners, and he touches pleasantly on that subject. His secret of why these meals taste so good is explained in his reply to a lady who had just helped herself to a second serving of bass despite the fact that "she just couldn't eat fish at home." To her he said:

"Oh, I just stir in a few laughs, add a little smell of white cedar and a touch of wood smoke, and some of our good Canadian fresh air. It makes quite a dish." That's the way with Clint's book. As reading fare, it makes quite a dish.

Published by Duell, Sloan and Pierce, Inc., 270 Madison Avenue, New York, N. Y., and obtainable from our Book Department. Price $3.50.

New Process Forecasts Wider Use of Titanium

PILOT-PLANT operations at Boulder City, Nev., by the U. S. Bureau of Mines may lead to a wider use of titanium, which is described as a light metal of exceptional chemical and physical properties. Ductile in the pure state so that it can be fabricated and worked, it is said to be superior to aluminum and magnesium on the basis of strength and weight and to possess many of the valuable properties of stainless steel. However, it has been difficult to produce in the pure state, and that has limited its industrial application.

By the new process developed by the Bureau of Mines, pure titanium chloride is dripped onto molten magnesium in the presence of helium under slight pressure. The mixture thus obtained is wet-ground, screened, and leached with dilute hydrochloric acid, yielding a powder that is pressed into briquettes and sintered at 1830°F. under a high vacuum to remove the hydrogen picked up during leaching. The sintered material, it is claimed, can be rolled at room temperature with reductions of 20 percent before annealing, or of as much as 75 percent at 1200°F. Output of the pilot plant is about 100 pounds of pure titanium a week.

Though cost of production by the improved method is still relatively high, the expectations are that large-scale operations will effect some economies. Be that as it may, the simplified reduction furnace promises to make pure titanium available for uses where its favorable properties outweigh price and for the manufacture of airplane parts; diaphragms that are maintained under tension; spindles, spools, and other working components of textile machinery; certain types of springs; and other products where lightness, strength, and resistance to corrosion are vital factors.

Industrial Notes



Designed for production-line assembly, a pneumatic hand tool for crimping solderless electrical terminals onto wires has been announced by Aircraft Marine Products. Built for wire sizes from 22 to 14, the unit makes complete connections as fast as operator can insert the wire and pull the trigger. The toggle action employed provides 2000 pounds crimping pressure with air at 85 pounds psi. and low consumption. Hardened tool-steel crimping jaws are readily interchangeable for the various types of solderless terminals manufactured by the company and accommodate a number of sizes. Tool is said to be small enough for service in hard-to-reach spots and light enough to prevent operator fatigue when used continuously.

Detection of faulty bearings in engines of automotive vehicles is the purpose of a portable device developed by the Federal-Mogul Corporation. It does its work without the necessity of tearing down the engine, it is claimed; only involves dropping the oil pan and hooking up the equipment to determine the condition of all main, connecting-rod, and camshaft bearings, as well as of the oil lines in any full-pressure lubricating system. Detector supplies clean oil at constant pressure and indicates leaky, tight, or defective bearings or plugged lines by the volume of the escaping oil.

Rubber-bonded abrasives in stick form are being made by the Sandusky Abrasive Wheel Company for a wide variety of metal-finishing operations. The material can be cut with a jacknife, file, grinding wheel, hack or band saw and enables tool and die men, patternmakers, etc., to provide themselves with special shapes for cleaning, deburring, and polishing threads, grooves, corners, curves, and other contours. Sticks are available in fine, medium, and coarse grains; in 3-, 6-, and 8-inch lengths; and in four standard shapes—rectangular, square, triangular, and round.

Made in two sizes for light and heavy duty, the improved Kant-Mar hammer announced by Schmidgall Products is said to be tough enough to take punishment and yet soft enough so as not to damage delicate surfaces. Either size is available in a plain model or with replaceable tips of Velv-Alum, a precision-turned special aluminum alloy that does not chip. Handle of selected-grade hickory fits into oval hole in head to insure tight hold.

Two new air arbor presses that combine the features of arbor and kick-type machines have been designed by Air-Trol to supplement its line of fast-action, spring-return pneumatic cylinders for material-holding operations. One is a heavy-duty model weighing 72 pounds, and the other a 40-pound unit delivering, respectively, around ¾ and ¼ ton at 150 pounds line pressure. Presses are set for a given application by regulating the air pressure, thus always insuring just enough to do uniform work and to obviate the danger of crushing incident



to manual operation. When controlled by foot valve to leave hands free, machines deliver full stroke with less than 1 inch movement of pedal. Cylinder brackets are adjustable on the column to provide a ram clearance ranging from 0 to 6 inches.

Ingersoll-Rand Company has recently added a 4-point detachable bit of the stud type, designated as the Stud Jackbit, to its line of rock-drilling equipment. The new design, shown at the right, permits making the bit, stud, and drill rod of materials best suited for the functions peculiar to each and to place more material especially at points in the bit where it is most needed. The result is a tool of increased strength which, in combination with carefully worked out wing curves that allow gauge reductions of 1/16 inch and less, makes it possible to drill faster than normally, as well as to start holes with smaller bits and still bottom them the same size as before. The bit is said to retain its proportions with successive resharpenings and to perform like a new one throughout its lifetime.



The Jackstud is factory-made of high-grade carburized alloy steel. One end is deeply furrowed and cone-shaped and is driven cold into the heated rod. This work can be done on an I-R sharpener with the aid of a set of special accessories. The bit end has case-hardened reverse buttress threads that keep their shape and extend right up to the driving shoulder—there is no undercut into which the bit skirt can upset and become locked. Bit is therefore easily detached from the rod. Further information is contained in a bulletin—Form 4062—obtainable from Ingersoll-Rand Company, 11 Broadway, New York 4, N. Y., or any of its branch offices.

An inorganic membrane for use with waterproofing compounds has been introduced by the Lexington Supply Company. The fabric is made of Owens-Corning Fiberglas and is of open-mesh weave to permit full impregnation by coal tar or by asphalt bitumens. So treated it adheres firmly to rough and irregular surfaces, molding itself to the contours, and is suitable for the protection of roofs, brick and concrete walls above or below ground, and for many other purposes in the construction industry. Called Glasfab, the yarn does not rot and does not char or burn when a hot compound is applied. Neither do the fibers carry moisture into the waterproofing by capillary action nor permit the escape of volatile oils essential to its durability. Because of these inherent qualities of glass, the membrane is said to give the impregnating materials much longer life than they have normally.

Experimental work conducted in the chemistry laboratories of the University of Michigan have resulted in a machine that makes use of a stream of electrons to study the atomic structure of metals and gases and to identify invisible films of foreign materials on metal surfaces. The unit is based on a model developed

NAYLOR Light-weight PIPE...

AT ITS BEST ON JOBS LIKE THESE



- High pressure hydraulic lines
- High and low pressure air lines
- De-Watering and drainage lines
- Ventilating pipe
- Water supply lines
- Sludge lines

Sizes from 4" to 30" in diameter with fittings, connections and fabrications to meet any mining requirements.

NAYLOR PIPE COMPANY

1245 East 92nd Street • Chicago 19, Illinois

New York Office: 350 Madison Avenue • New York 17, N. Y.

by Prof. Lawrence O. Brockway and consists basically of a vacuum chamber with a holder for a specimen in the center and another for a photographic plate at the opposite end of the source of electrons. The metal to be examined interrupts the flow of 40,000-volt electrons produced by the machine, causing them to be deflected and to expose the negative. Because each metal breaks up the stream in a distinct pattern, the photographs obtained differ, and it is therefore possible to identify unknown substances by comparing the diffraction patterns with those of substances previously identified. This new method of analyzing metal surfaces is said to have numerous fields of practical application, including painting, lubrication, electroplating, and welding.

Officials of the Refractories Division of The Babcock & Wilcox Company have announced the development of a concrete, designated as B & W Kaocast, that readily withstands temperatures as high as 3000°F. The material may be poured like ordinary concrete or applied by ramming, and may be used for the fabrication of special shapes or to form part or all of the furnace lining. In laboratory and protracted service tests the material is said to have shown excellent stability and resistance to disintegration under repeated heating and cooling cycles, small volume change on initial firing, and negligible shrinkage and expansion under continuous service at high temperatures. Among other applications listed for the refractory are: as a covering for studs in water-cooled furnace walls, for making high-temperature baffles, and for deep-patching of spalled or eroded brickwork.

ERASER OF GLASS

The ends of myriads of hair-thin glass fibers encased in a plastic holder form the rubbing surface of a new typewriter eraser produced by The Eraser Company, Syracuse, N. Y., under the name of Rush-Fybrglass. The fiber sheaf is moved in or out like the lead in a mechanical pencil and can be replaced by a refill when depleted. The maker claims it works with such light pressure that no shield is needed to protect carbon copies from smudging.

TUBELESS TIRE

Cross section of a tubeless pneumatic tire now being tested by The B. F. Goodrich Company, Akron, Ohio. The puncture sealant permits it to be driven over upturned spikes without loss of air. A taxicab fleet in one city, Ohio State police cars, and some privately owned cars are using the tires experimentally and they are now being offered for limited sale. The tire is believed to have attained a goal sought by manufacturers since the advent of the automobile era.

For deep-sea diving operations, Westinghouse Electric Corporation has produced a 1000-watt incandescent light that is about the size of the average household lamp. It is not suitable for ordinary use, however, because its filament, which almost touches the bulb, would cause the light to burn out instantly unless surrounded by water to keep it cool.

To discover the oldest installations of 85 percent Magnesia insulation still serving effectively, The Magnesia Insulation Manufacturers Association has announced a contest with sixteen prizes as awards. The first is a $100 Savings Bond, and there are five second and ten third awards. Each second-prize winner will receive a Telechron electric cyclometer-type clock, and each third an electric desk clock. Entry blanks may be obtained from the association, 1317 F Street, N. W., Washington 4, D.C. Contest closes on October 10.

Draw-Kleen, if it does all that is claimed for it, should prove a boon to draftsmen, especially in humid weather. The material is in the form of soft, dry crumbles and is dispensed from a shaker-top can. It is sprinkled on paper or tracing cloth before drawing is started and brushed off after rubbing when completed, leaving surfaces free from perspiration, dirt, and pencil smudges. Draw-Kleen is a product of Craftint Manufacturing Company, Cleveland 10, Ohio, and is also suitable for cleaning blueprints, artwork, maps, documents, etc.

"Here's Your Pumping Secret to LOW Maintenance Costs!.."

"Mister, if you want LOW maintenance costs in your piping system... Victaulic COUPLINGS and FITTINGS are your answer!

"Victaulic COUPLINGS give piping systems a *union at every joint*. This, with the two-bolt simplicity of Victaulic Couplings, means that *any* pipe length, valve, or fitting can be quickly, easily unbuttoned and removed for repair or replacement – without damage to pipe ends or couplings – without backing off adjoining sections!

"Also, Victaulic Couplings are engineered to grip pipe ends *all around*. Joints are positive-locked, slip-proof, can't pull out or blow off under pressure, vibration or sag... with expansion-contraction taken care of *automatically!*

"And that's only half of it. Victaulic FITTINGS are the perfect running mate for Victaulic Couplings when it comes to keeping costs *down*. The long-and-easy sweeps designed into Victaulic Fittings reduce internal friction to a minimum... lowering pumping costs *yet increasing delivery!*

"So, Mister, remember... for LOW COSTS in both maintenance and pumping – make your piping system ALL Victaulic!"

Write for new Victaulic Catalog and Engineering Manual

VICTAULIC COMPANY OF AMERICA

30 ROCKEFELLER PLAZA, NEW YORK 20, N. Y.

Victaulic, Inc., 727 W. 7th St., Los Angeles 14, Calif.

Victaulic Company of Canada, Ltd., 200 Bay St., Toronto 1

For export outside U. S. and Canada: PIPECO Couplings and Fittings: Pipe Couplings, Inc., 30 Rockefeller Plaza, New York 20, N. Y.

Have you considered Victaulic for your piping requirements?

Sizes – ¾" through 60"

SELF-ALIGNING PIPE COUPLINGS

VICTAULIC

EFFICIENT FULL-FLOW FITTINGS

Copyright 1947, by Victaulic Co. of America



the Forgesmithing factor in "OK" steel forgings

● Mighty as is the power of the forging press, the long acquired skill of the forgesmith is a most vital factor. To produce correct grain flow without impact damage to the structure of the steel is a matter of personal skill. The metal is formed by a powerful squeeze which penetrates throughout the ingot. The proper application of this squeeze to produce a forging of uniform structure is skill from experience.

National Forge standards call for careful pre-heating ("soaking") to the prescribed forging temperature, completion of the forgesmithing before the ingot cools below safe working heat and careful temperature control after forging to prevent cooling strains impairing the strength of the steel. As National Forge makes its own basic electric steel, it has the advantage of working with steel that is specifically made for each forging under strict metallurgical control.

Let us give you the latest facts and data applying to the type of steel forgings required in your plant or product.

National Forge
AND ORDNANCE COMPANY
Irvine, Warren County, Pennsylvania

NEW AIR LINE FILTER

GIVES SURER, LONGER PROTECTION AGAINST MOISTURE



Magnified Section of Filter Element

More positive removal of moisture results from a special baffling arrangement plus a newly-developed method of "felting" and impregnating micronic fibres. Moisture not deflected by the baffle is required to make hundreds of sharp turns through the minute interstices, impinging on the hydrophobic fibre structure, then draining freely to the collecting chamber. Channeling is positively prevented by the resinous impregnation.

Longer replacement-free service results from non-wicking property of the fibres. Accumulated moisture drains readily into extra-large collection chamber below filtering cartridge. Simple, sturdy housing is quickly disassembled for cartridge replacement by removing single cap nut.

MICRO-KLEAN Compressed Air Filter models now available handle up to 40 cfm of free air at pressures up to 125 psi. Larger capacity units in preparation.

Cuno MICRO-KLEAN Compressed Air Line Filters and replaceable cartridges are manufactured by the company whose filters are used more often in industry than any other brand.

Because it extracts the maximum amount of entrained moisture and dirt without requiring frequent cartridge replacement . . . the new Cuno MICRO-KLEAN is ideal for filtering compressed air under severe moisture conditions.



CUNO

Fluid Conditioning

REMOVES MORE SIZES OF SOLIDS FROM MORE TYPES OF FLUIDS

AUTO-KLEAN
General service down to .0035". Disc-type. Continuously cleanable.



FLO-KLEAN
For highly abrasive solids down to .0025". Wire-wound. Continuously cleanable.

MICRO-KLEAN
Micronic-type. Impregnated fibre. "Graded Density in Depth" cuts replacement cost.

COOLANT-KLEAN
Low-cost unit filtration of grinder coolant. Fabric-type element.

SEND COUPON FOR FREE FACTS TO FIT YOUR INSTALLATION

CUNO ENGINEERING CORPORATION
1710 South Vine Street,
Meriden, Conn.

Please have nearest Cuno representative provide information on Cuno Model 181G Compressed Air Filter.

Name ..... Title .....

Company .....

Address .....

For 9 out of 10 Stoker Jobs

one of these 3 C-E types is the best answer

Single Retort Underfeed and Spreader Stokers are far and away the most widely used types these days, accounting for about 90 of every 100 stokers installed under boilers rated from 50 hp up.

The high percentage of C-E Stokers selected in this category is indicative of how well these three types, described here, blanket this field.

And for the remaining 10 percent, C-E also has its modern designs of Multiple Retort, Traveling and Chain Grate Stokers, — all of them leaders in their respective fields.

So whether your plant is one of the 90 percent group or one of the 10 percent, you can turn to C-E with complete confidence that you will get the right answer for your requirements. You will also have the satisfaction of knowing that your stoker reflects the experience accumulated in installing over 19,500 stokers of all types, above residence size, to serve more than 55,000,000 sq ft of boiler heating surface. This is Combustion Engineering's record to date and no other stoker manufacturer in the country can match it. B-151



SPREADER STOKER — Approximate Application Range — 150 boiler hp to largest units suitable for stoker firing. A simple, rugged stoker designed to burn a wider variety of fuels than any other type of mechanical firing. Hopper, feeding and distributing mechanism, variable-speed drive and motor are combined in a compact unit. Rotating spreader blades feed coal into the furnace in crisscrossing streams which assure uniform distribution. Fines are burned in suspension and the rest of the coal is burned on a grate — either dumping or continuous discharge type. Grate surface is zoned for regulating air admission and to facilitate cleaning.



TYPE E STOKER — Approximate Application Range — 150 to 600 boiler hp. A single-retort underfeed stoker designed to burn a wide variety of bituminous coals. Ram feed is supplemented by a reciprocating sliding bottom. Grate surface consists of hollow, air-cooled grate bars, alternately fixed and moving, to condition the fuel bed and assure its steady movement toward the dump trays. Air supply under zoned control with provision for introducing air over the fire. Steam, electric or hydraulic drive.



SKELLY STOKER — Approximate Application Range — 20 to 200 boiler hp. A compact, self-contained unit offering all the advantages of underfeed firing. Moving grate bars assure lateral distribution of fuel and maintain a clean porous fire. Cantilever dump grates of non-avalanching type simplify ash removal. Integral forced-draft fan, with inlet control, permits positive regulation of air-coal ratio. Sixteen rates of coal feed through variable-speed transmission. Automatic control is standard equipment. Timken bearing equipped. Alemite lubrication throughout.

COMBUSTION C-E **ENGINEERING**

200 MADISON AVENUE NEW YORK 16, N. Y.

Special multi-stage ejector for service in a processing plant.

A single-stage, twin-element ejector mounted on a surface-type combination precooler and aftercooler.

GETTING THE MOST
out of a vacuum

The process operator who is trying to boost production, cut costs, or improve product quality knows that his vacuum-producing equipment must be exactly suited to his specific application, and that it must be capable of sustained, trouble-free operation.

This is the kind of performance you will get from Ingersoll-Rand Steam-Jet Ejectors, Condensing Equipment, and Reciprocating Dry Vacuum Pumps.

If you have a problem or process that requires a vacuum, why not consult Ingersoll-Rand? Perhaps our specialists can suggest a new application for vacuum producing equipment that will enable you to get the most from your manufacturing process—the most in processing efficiencies—the most in reduction of product cost—the most in product improvement.

Reciprocating dry vacuum pump.

A two-stage, single-element ejector mounted on a direct-contact type intercondenser.

A large vacuum booster for refining service.

Ingersoll-Rand

11 Broadway, New York 4, N. Y.

4-858

FOR ALL MAJOR SERVICES
IN PRINCIPAL INDUSTRIES

Walworth Valves and Fittings

assure low cost dependable performance

Walworth manufactures a **complete line** of valves and pipe fittings for ALL major services in principal industries. All Walworth products are made to the highest standards of quality, both as to dimensional accuracy and metallurgical properties. In design, construction, and performance, they reflect Walworth's 105 years of "know how" in the manufacture of quality valves and fittings.

Your Walworth distributor will give you full information on the **complete line** of Walworth steel, iron, and bronze valves, and pipe fittings; also Walworth Lubricated Plug Valves, and Walseal* valves, fittings and flanges. Ask for this information today.

*Patented–Reg. U. S. Pat. Off.

WALWORTH
valves and fittings
60 EAST 42nd STREET, NEW YORK 17, N. Y.

DISTRIBUTORS IN PRINCIPAL CENTERS
THROUGHOUT THE WORLD

No. 95
150-Pound
Bronze
Valve

Renewable Disc

No. 225P
350-Pound
Bronze
Valve



"500 Brinell" Seat & Disc

No. 709
Iron Body
Saddle
Gate
Valve

No. 1671F
Steel
Ball Bearing
Lubricated
Valve
Plug



Pressure-
Seal
Steel
Valve

No. 726F
Iron Body
Wedge
Gate
Valve



DUST and DIRT CAN'T HURT WAGNER *cp* MOTORS*

**Totally-Enclosed Fan-Cooled Motors are SEALED against Harm . . .*

THEY'RE built to take it . . . They're protected against dust, dirt, grit, steel chips, abrasives, and other destructive elements that would tear the heart out of ordinary motors. That's why you find thousands of Wagner totally-enclosed fan-cooled motors giving dependable service day after day, year after year, doing the dirty jobs in industry without asking favors.

If you use motors, it will pay you to investigate Wagner—A complete line . . . built by engineers who know how to build quality motors that will help you maintain peak production. Users of Wagner motors also profit by our quick, convenient, nationwide service facilities.

Contact any of our twenty-nine branch offices, located in principal cities and manned by trained field engineers ready to give you advice on all of your motor problems. Bulletins on the complete line of quality motors will be sent upon request. Address Wagner Electric Corporation, 6418 Plymouth Avenue, St. Louis 14, Mo.



Pictured above is a Wagner totally-enclosed fan-cooled motor. Wagner makes a complete range of motors for every application.

M47-8

Wagner Electric Corporation EST. WE 1891

Consult Wagner Engineers on all Electric Motor Problems



BRIDGE BRAKES • POWER AND DISTRIBUTION TRANSFORMERS • MOTORS • UNIT SUBSTATIONS

ELECTRICAL AND AUTOMOTIVE PRODUCTS



. . . take "CYLINDER WEAR"

Cook Graphitic Iron Plain Rings feature: Excess carbon in the form of graphite flakes to ease the ring over dry spots in the cylinder—Porosity to facilitate spreading of lubrication—Rapid work-hardening ability to minimize friction, prolong life—Freedom from wear-inducing steel-like inclusions (carbides).

Cylinder wear results from the rubbing action of the piston rings against the cylinder wall. The rate of wear is influenced by many variables, but chiefly by the material of which the rings are made—just as the rate of wear of a shaft is mainly determined by the material in the bearing. Where you have rings of high friction materials you add to your operation expense sheet the hidden cost items of early cylinder replacement—higher and higher fuel consumption as wear progresses—lost power—frequent shutdowns for repairs.

Cook Graphitic Iron Rings are outstanding in their friction-reducing properties. Test after test both in field and laboratory has proven this indisputable fact. The exclusive material of which they are made and their process of manufacture enable them to keep friction and wear to a minimum and thus prolong cylinder life. Cook Rings are custom made for severe service conditions and occupy a unique position in this field.

If your rate of cylinder wear is high, it will pay you to investigate Cook Rings. For the complete story, write today. ATTENTION DEPT. 6-C.

Sealing Pressures

Since 1888

C. LEE COOK MANUFACTURING CO.
INCORPORATED
LOUISVILLE, KY.

BALTIMORE • BOSTON • CHICAGO • CLEVELAND
HOUSTON • LOS ANGELES • MOBILE • NEW ORLEANS
NEW YORK • SAN FRANCISCO • TULSA

"Better Piston Rings for Higher Efficiency—through Metallurgy"



Texrope *VARIABLE* Speed Drive ... the practical way to get *Accurate Speed Control*

- To regulate a machine tool to suit variations in job, material, or individual workman
- To control the volume of air from heating and ventilating fans
- To vary the speed of a pump, spinning frame, conveyor, rock crusher or grinding wheel
- *Wherever* the ability to change operating speeds at will can add to efficiency, output or economy —

Install Texrope Variable Speed Drives!

These flexible drives use economical constant speed motors. They provide infinite speed variations within their ranges — quickly, easily, accurately.

Vari-Pitch sheaves using A, B, C, D or E belts are available for stationary or motion control, with range up to 25% per sheave; *Vari-Pitch* sheaves using Q or R wide belts allow variations up to 100%; *Vari-Pitch* speed changers permit ranges up to 375%. There are types and sizes to suit all needs, from fractional to 300 hp!

Texrope offers the *most complete* line of variable speed drives made . . . engineered and built by Allis-Chalmers, originator of the multiple V-belt drive. See Sweet's Catalog, or call your nearby A-C office or dealer for Bulletin 20B6051G. ALLIS-CHALMERS, MILWAUKEE 1, WIS.

A 2200

TEXROPE .. Greatest Name in V-Belt Drives

"Super 7" V-BELTS
Five Types — Sizes to suit every power transmission job.

Texsteel, Texdrive, "Magic-Grip"
— sheaves in a full range of sizes, grooves.

"Vari-Pitch" SHEAVES
Exact variations in speed, stationery or motion control.



SPEED CHANGERS
Speed variations up to 375% at the turn of a crank.

ENGINEERING
Finest V-Belt engineering talent in the world—at your call.

TEXROPE "Super 7" V-Belts result from the cooperative research of two great companies — Allis-Chalmers and B. F. Goodrich. They are sold only by A-C.

ALLIS-CHALMERS

One of the Big 3 in Electric Power Equipment — Biggest of All in Range of Industrial Products

1847 1947
A CENTURY OF SERVICE to Industry THAT MADE America Great

The TERRY TURBINE



FOR SLOW SPEED DRIVES -
ACCURATELY DESIGNED TERRY TURBO-GEAR UNITS

For driving slow speed fans, D. C. generators, paper machines, large pumps, and the like, Terry Turbo-Gear Units offer many advantages.

—The Turbine can be — A Solid Wheel Type — A Single Stage Impulse — or a Multi-Stage Impulse Design, whichever fits your requirements best.

—The Gear is not just an ordinary gear but is a carefully designed and constructed power transmission unit built entirely for the high speeds encountered in turbine practice. Each gear is engineered for the job conditions. Forced feed lubrication is used on the bearings and the meshing teeth. The teeth are double helical and are generated on precision gear cutting machines. The bearings are of the Babbitt lined sleeve type and are unusually heavy so as to prevent distortion under load. All rotating parts are carefully balanced.

A typical Terry Turbo-Gear set is shown above. This unit delivers 300 H.P. with steam conditions of 250 lbs. 150° and 20 lbs. back pressure. The turbine is of the axial flow single stage type and operates at 4230 R.P.M. The gear reduces this speed to 470 R.P.M. The governor is of the oil relay variable speed type and is equipped with remote speed control.

If you have a specific turbine drive job, a Terry engineer will be glad to discuss it with you. — Descriptive bulletins on request.

T-1164

THE TERRY STEAM TURBINE COMPANY
TERRY SQUARE, HARTFORD, CONN.



Simplifying the choice of Ropes for Dragline Excavators



TYPE U
independent
wire rope core



TYPE W
independent
wire rope core



TYPE W
fiber core

If you own a dragline machine, spend two minutes reading the following paragraphs. Then keep this page for reference. It will help you select the proper wire rope for every part of your outfit.

DRAGLINES are subjected more to abrasive wear than to bending fatigue. Therefore a Bethlehem Purple Strand 6 x 19 Type U rope is widely chosen, for the Type U has fairly large outer wires. Lang lay should always be used in this service. Independent wire rope core is recommended.

HOIST LINES generally travel over only one sheave; hence they are not as affected by wear as by bending fatigue and crushing. Bethlehem Purple Strand 6 x 19 Type W, lang lay, is widely specified. Independent wire rope core is generally used. Form-Set (preformed) construction optional.

BOOM LINES are more or less stationary. With little movement, there is little wear. A sound choice is Purple Strand 6 x 19 Type W, regular lay, independent wire rope or fiber core. Lang lay is also commonly used.

Further details are available through your nearest Bethlehem field engineer. Always check with him in cases of doubt. Part of his job is to help you get the *correct* wire ropes.

BETHLEHEM STEEL COMPANY, BETHLEHEM, PA.

On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation

When you think WIRE ROPE . . . think BETHLEHEM

ON 1,220,000



Keeps its bearings *in a "dust bowl"*

Ordinarily, we wouldn't recommend that you use an open motor on a job like this. This Tri-Clad motor drives a boiler-feed pump in the National Gypsum Company plant at Clarence Center, N. Y. The air surrounding the motor is constantly filled with gypsum dust which must be kept out of the bearings. And it *has* been kept out of the bearings of this Tri-Clad motor, thanks to its specially designed bearing housing and seals. We believe that the Tri-Clad motor you see here proves that even where dust, moisture, or some other hazard is extremely severe for open-motor applications, the extra protection afforded by Tri-Clad motor construction results in longer motor life and lower upkeep.

and now—THE TOUGHEST TRI-CLAD YET

Newest addition to the Tri-Clad motor family is the Tri-Clad totally enclosed, fan-cooled motor. It is designed for use in adverse atmospheres—in iron dust, out-of-doors, in hazardous areas, and chemical atmospheres. Available in both standard and explosion-proof types, this Tri-Clad motor gives you these important construction features:

- A cast-iron, double-wall frame which completely encloses and protects the windings and punchings.
- A nonshrinking compound around motor leads which protects motor interior from dust and moisture.
- A rotating labyrinth seal which further protects the motor interior from damage by foreign matter.

MOTORS

TRI CLAD

THE SYMBOL OF

EXTRA PROTECTION

Announcement of the Tri-Clad motor, back in 1940, ushered in a new concept of general-purpose motor design. Substantially increased horsepower-per-frame-size, was one feature. Smarter appearance was another. But what really sold more than a million Tri-Clad motors is the *extra protection* we built into them.

Often operating under conditions no general-purpose motor should be asked to meet, Tri-Clad motors built up an enviable record of war-time service. Today, with the "family" including dripproof motors, vertical motors, gear-motors, capacitor-motors, and totally enclosed motors, the Tri-Clad motor is, more than ever, the motor that means basic protection, dependable performance, and minimum upkeep. *Apparatus Dept., General Electric Company, Schenectady 5, N. Y.*



EXTRA PROTECTION... AGAINST PHYSICAL DAMAGE!

Rigid cast-iron frame and end shields protect vital motor parts from external abuse and prevent resonance. Because they're not at the mercy of a coat of paint, they strongly resist chemical attack and dampness. Cast iron also gives you tight, *metal-to-metal* fits between end shields and frame.

EXTRA PROTECTION... AGAINST ELECTRICAL BREAKDOWN!

Motor windings of Formex* wire, together with improved insulating materials, reduce the chances of electrical failure. Heat is dissipated quickly — motor stays young for years and years!

EXTRA PROTECTION... AGAINST OPERATING WEAR AND TEAR!

Bearing design affords longer life, greater capacity, improved lubrication features. Bearing seals retain lubricant, keep out dirt. One-piece, cast-aluminum rotor is practically indestructible.

*Trade-mark reg. U. S. Pat. Off.

GENERAL ELECTRIC

750—285

TRI CLAD

REG. U.S. PAT. OFF.

MOTORS

- OPEN (DRIPPROOF)
- TOTALLY ENCLOSED
- EXPLOSION-PROOF

WHAT IS OPERATOR CONTROL?



OPERATOR CONTROL means gradual or instantaneous starting and stopping.

OPERATOR CONTROL MEANS ACCURACY because it permits smooth lowering and lifting as slowly or as rapidly as desired.

OPERATOR CONTROL MEANS SAFETY, because it helps prevent accidents that might otherwise occur in jerky lowering and hoisting, or in hand lifting.

OPERATOR CONTROL MEANS ECONOMY because it eliminates motion wasted in operating chain blocks, or lifting by hand.

In addition to Operator Control, Ingersoll-Rand Overhead Air Hoists offer other time and money saving advantages . . . increased efficiency and output . . . tested durability . . . reduced maintenance and operation costs . . . minimum operator fatigue.

Our experienced hoist engineers will be glad to help you solve your hoist problems. Phone our nearest branch office or write for Bulletin 5020.

Ingersoll-Rand

11 Broadway, New York 4, N. Y.

66-8

COMPRESSORS · AIR TOOLS · ROCK DRILLS · TURBO BLOWERS · CONDENSERS · CENTRIFUGAL PUMPS · OIL AND GAS ENGINES

STRENGTH

for Safety and Long-Time Service



For 2000, 3000 and 6000 pounds service — Sizes 1/8" to 6"

SCREW END TYPE



For schedules 40, 80 and 160 pipe — Sizes 1/8" to 4"

SOCKET WELD TYPE

Vogt Ells, Tees, Crosses, etc., are forged from carbon steel or various alloys to meet specific operating conditions. Catalog F-8 will aid you in their selection and proper application.

Shocks and stresses imposed by high pressures and high temperatures are taken in their stride because Vogt fittings are uniform in structure, fine grained, and free from porosity . . . the superior product of laboratory controlled materials and giant forging hammers and upsetters. These properties also give higher resistance to erosive and corrosive conditions, thereby adding to service life expectancy in steam plants, petroleum refineries, chemical plants and related industries.

HENRY VOGT MACHINE CO., INC.
Louisville 10, Kentucky
BRANCH OFFICES: NEW YORK • PHILADELPHIA • CLEVELAND • CHICAGO • DALLAS

Vogt DROP FORGED STEEL FITTINGS

"Flex-Disc"

CLUTCHES for MACHINE TOOLS

Thoroughly proved by eight years of very severe service in I-R Mobil-Air Compressors, Flex-Disc Clutches are now being applied to machine tools. Their advantages are briefly:

1. No back-lash or chatter. There is a positive connection between driving member and driving disc through resilient integral links.

2. Positive release. The resilient links center driving disc between driven plates of clutch permitting indefinite operation without dragging or heating.

3. Easy Maintenance. The driving disc is constructed with interlocking segments which may be removed for relining without dismantling clutch or machine.

4. Interchangeability. The several sizes of Flex-Disc Clutches may be put in place of corresponding sizes of conventional gear tooth driven clutches.

Our illustration shows a "Flex-Disc" driving plate replacing an internal gear drive ring and a gear tooth driving disc on a milling machine.

CUSTOM-MADE CLUTCHES

To meet special operating conditions. We will cooperate with you in solving any special clutch problems whether your order is for a few or for thousands.

INDUSTRIAL CLUTCH CORPORATION

Waukesha Wisconsin

The REAL MEASURE of ENGINE VALUE is "H. P. HOURS" of POWER SERVICE



It isn't the original H.P. rating of an engine that counts but rather, the number of *H.P. Hours* of power service it will deliver during its lifetime. This is the real measure of engine *value*.

Wisconsin Air-Cooled Engines deliver the most H.P. Hours because they are designed and built for rugged, heavy-duty service. For example: every Wisconsin Engine, from the smallest to the largest, runs on Timken tapered roller bearings at both ends of the crankshaft to take up end-thrust and provide the best protection against bearing failure . . . at the same time assuring a smooth-running engine. This is just one typical detail that stands back of "Most H.P. Hours" of on-the-job power service.

You can't go wrong if you specify "Wisconsin Air-Cooled Engines" to meet your power requirements, within a 2 to 30 hp. power range.

Wisconsin Engines are available in a complete range of types and sizes (all 4-cycle) from 2 to 30 hp.

WISCONSIN MOTOR Corporation
MILWAUKEE 14, WISCONSIN
WORLD'S LARGEST BUILDERS OF HEAVY-DUTY AIR-COOLED ENGINES



MAXIM EQUIPPED FOR GOOD PUBLIC RELATIONS

A portable compressor is apt to spend its service life in many locations where noise is a nuisance to nearby homes and offices. It is good public relations to provide adequate silencing and good practice to choose Maxims for this job. For superior silencing of engine exhaust and intake, compressor intake, steam or air blow-off; for spark arresting or silencing with the heat recovery feature, specify Maxims. Detailed bulletins on request.

THE MAXIM SILENCER COMPANY
61 HOMESTEAD AVENUE, HARTFORD 1, CONN.

MAXIM SILENCERS

As advertised in TIME and NEWSWEEK

New filter cleans all the oil all the time

ARE YOU PAYING for full-flow oil filtration—and not getting it? That's what happens with conventional filters which clean only *part* of the oil at a time. Grit gets through, damages equipment.

AIR-MAZE ENGINEERS have the answer to this problem. It's the new Air-Maze Type "O", an entirely different oil filter which gives truly full-flow performance because it filters *all of the oil all of the time!*

THE TYPE "O" EMPLOYS the same Air-Maze filtering principle that protected America's finest aircraft engines in over *5 billion miles* of wartime flying. And it has been thoroughly service-proved in numerous industrial lubrication, hydraulic and fuel systems.



HOW IT WORKS: The filter's unusual design incorporates many times more effective filtering area than ordinary filters, thus providing large capacity and low pressure drop. It consists of multiple filter discs, made of extremely fine bronze screen cloth, stacked over a perforated tube. Pressures are equalized, because each disc permits filtration on *both sides*. Standard square screen opening is .0032". Filtration becomes finer as dirt collects.

RESULTS: When oil is filtered by Air-Maze, equipment operates better and lasts longer. There's always a plentiful supply of grit-free oil. All-metal disc assembly is easy to clean, lasts indefinitely.

HAVE YOU A FILTERING PROBLEM? If it involves oil,* send for your free copy of the new Air-Maze bulletin on "full-flow" filters. And remember—if you build or use engines, compressors, air conditioning and ventilating equipment, or any device using air or liquids—the chances are there is an Air-Maze engineered filter to serve you better. Write Air-Maze Corporation, Cleveland 5, Ohio.

**Note: Because most existing car and truck lubrication systems are not designed for full-flow filters, Air-Maze Type "O" are not recommended for replacement purposes.*

AIR-MAZE
The Filter Engineers

for AIR COMPRESSORS *and* WATER PUMPS



Class 9013
type ASG

PRESSURE SWITCH

250 lbs. pressure limit
10 to 45 lbs. differential

• A standard controller for motor-driven air compressors and water pumps. Heavy contacts, with silver permanently bonded to the heavy bronze backing. Generous electrical ratings. Four ⅞ inch knockouts for ½ inch conduit are provided for convenient wiring.

Modern black enameled steel cover. Corrosion-resisting inner parts. High-grade impregnated fabric diaphragm. Oil-resisting type also available.

Write for Bulletin • illustrations, specifications of Square D pressure switches and related devices. Address Square D Company, 4041 North Richards Street, Milwaukee 12, Wis.

SQUARE D COMPANY

DETROIT • MILWAUKEE • LOS ANGELES

SQUARE D CANADA, LTD., TORONTO, ONTARIO • SQUARE D de MEXICO, S.A., MEXICO CITY, D.F.

Nicholson Catalog 546 Shows

FAST ACTING · SLOW WEARING Control Valves

for Every Operating Purpose



Style E, 4-Way

Featuring specially treated seats that don't cut out, Nicholson cylinder control valves are heavy-bodied, generously packed, fast-acting units, recognized for the way they stand up. Metal combinations for specific needs. Lever, foot, solenoid, motor types for all mediums. Pressures to 5000 lbs.

Catalog 546 or see Sweet's

REPRESENTATIVE INSTALLATIONS

Brakes · Clutches
Gates · Dumps
Control Instruments
Air Hoists
Steel Furnaces
Large Gate Valves
Automatic Controls
Larry Cars · Cranes
Bus Doors
Locomotives

W. H. NICHOLSON & CO.
180 OREGON ST.
WILKES-BARRE PA.



B S & B SAFETY HEADS
Rupture discs burst in tension at predetermined pressures and temperatures. Provide full-throated, positive relief from over-pressure. Act instantly.

Two Proven Methods of

PRESSURE RELIEF

NATURE'S SAFETY HEADS
Volcanoes provide an escape of terrific internal pressures through earth's crust . . . relieving stresses which otherwise would cause earthquakes. Mother Nature's own SAFETY HEADS.

A controlled weak point . . . that's what the B S & B SAFETY HEAD provides. You determine the limit of temperature and pressure . . . a SAFETY HEAD guarantees protection within 5% of that limit! No other pressure relief device can approach the relief capacity of a SAFETY HEAD in a given diameter.

Can be installed wherever you have liquid or gas under pressure . . . 5 to 25,000 psi. Each is made for your individual needs. Thousands of plant owners throughout the world have turned over their pressure relief problems to SAFETY HEADS. Put them to work for you!

Write today for complete information, specifications, installation data. Address the Special Products Division, Black, Sivalls & Bryson, Inc., Power and Light Building, Kansas City 6, Missouri.

FOREIGN INQUIRIES INVITED — Cable Address: BLACK, KANSAS CITY, U.S.A.

BLACK, SIVALLS & BRYSON, INC.

EFFICIENCY · RELIABILITY

KANSAS CITY, MO. — OKLAHOMA CITY, OKLA.
CASPER, WYO. — CALGARY, ALTA.

R. C. PILOT VALVES FOR POSITIVE CONTROL

R-C Unloader Pilot Valves (plain or strainer type) are standard on many leading compressors...installed as replacements on thousands of compressors in all parts of the U.S.A. and overseas. The R-C valve—positive in action—cannot chatter...it's always in open or closed position. Adjustment is provided for any unload-to-load range from 3½" to 30% of maximum receiver pressure. Install an R-C Unloader Pilot valve—let performance prove its value. Specify air pressure and range of on-and-off operation desired. Write for price and recommendation.



R.C. PILOT VALVE
STRAINER TYPE

R. CONRADER CO.
1207 FRENCH STREET - ERIE, PA.
PILOT VALVES for Portable and Stationary Air Compressors provided with Unloaders

STOP THE GUK

KNOCK OUT AIRBORNE SOLIDS

. . . Catch oil emulsion and moisture with Norgren Filters. Proved. Fit any air line. Easy to clean, open waste cock, blow the GUK out.

Write for catalog 400. C. A. Norgren Co., 222 Santa Fe Drive, Denver 9, Colorado.

Norgren



WHY THIS COMPRESSOR DRIVE DELIVERS MORE POWER, LONGER

This compressor drive has

SCHIEREN DUXBAK BELT'S *EXTRA PULLEY GRIP* which comes from the clean, uniform open grain surface shown in this photomicrograph. Achieved by a special Schieren scouring process, this full-friction grip enables the belt to step up compressor output.

AUTOMATIC BELT TENSION CONTROL provided by this pivoted motor base. This means no slipping or burning of belt, instantaneous compensation for overload and minimum stress on belt and bearings. You can get complete details on the belt and the motor base on request, without obligation.



SC-14

CHAS. A. SCHIEREN COMPANY
35 FERRY STREET, NEW YORK 7, N. Y.
60 Front Street, W., Toronto, Ont.
Tanners and Manufacturers Since 1868
Branch Offices in Chicago, Dallas, Denver, Detroit, Lowell, Newark, New York, Philadelphia, Pittsburgh, Salt Lake City.

LEATHER PACKINGS

LEATHER BELTING

LEATHER SPECIALTIES



"Air Hold"

Speeds Up Paper Cutting

A NOPAK Model "D" Air Cylinder, used to operate the "hold-down" mechanism of this paper cutting machine, has increased its capacity substantially. Now, a quick flip of the NOPAK valve lever clamps and releases the stacks of paper, instantly, before and after cutting.

Slow, hand-manipulation of the screw clamp is eliminated — many more cuts-per-hour are made possible. Similar application and control of Air Power . . . with NOPAK Cylinders and Valves . . . can step-up productivity of your machines too.

NOPAK MODEL D AIR CYCLINDER

—is designed for vertical downward pushing power. Rod extension is through the mounting base. May be mounted on any horizontal flat base in which an opening can be provided.

REPRESENTATIVES IN PRINCIPAL CITIES

•

Ask your NOPAK Representative for a copy of the NOPAK Application Manual.

GALLAND-HENNING MFG. CO., 2759 S. 31st St., Milwaukee 7, Wis.

NOPAK

VALVES AND CYLINDERS

DESIGNED for AIR and HYDRAULIC SERVICE

A 5236-½HA



DRI AIR MAY BE INSTALLED BY SUSPENDING IT FROM THE PIPING WITHOUT ANY OTHER SUPPORT.

INCREASED PNEUMATIC EFFICIENCY WITH THIS AUTOMATIC SEPARATOR



PROTECT EQUIPMENT WITH

DriAir

SEPARATES • COLLECTS • DELIVERS

• DriAir separates and automatically ejects the condensed water and oil from compressed air lines, collects pipe scale and rust, delivers clean dry air to tools and other pneumatic equipment. This promotes better lubrication, reduces wear, increases life of tools and produces greater output. All internal parts are made of bronze or copper—resistant to corrosion and practically permanent.

A TYPICAL INSTALLATION SHOWING DRI AIR STANDING ON A CONCRETE FLOOR NEXT TO THE WALL.

WRITE FOR BULLETIN DA WHICH FULLY DESCRIBES THE CONSTRUCTION AND OPERATION OF THE DRIAIR.

NEW JERSEY METER CO.

"SPECIALISTS IN COMPRESSED AIR DEVICES"

PLAINFIELD, NEW JERSEY

You'll get CLEAN AIR CONTINUOUSLY with a *Dexter* AUTOMATIC AIR SEPARATOR


AIR GOES IN HERE
CLEAN DRY AIR COMES OUT HERE
AIR EXPANDS, WATER AND OIL VAPORS CONDENSE
DRY AIR GOES UP HERE
STRAINER REMOVES DIRT
ONLY MOISTURE, OIL AND DIRT GET THIS FAR
OIL AND MOISTURE COME OUT HERE

Clean air continuously means compressed air that is *always* free from water, oil and dirt.

With *clean air continuously* your pneumatic tools will work better and last longer — your cleaning, blasting and spraying will be free from spoilage — your pipe lines will be protected from freeze-ups — *you'll operate more economically.*

The Dexter Air Separator positively removes oil, water and dirt from compressed air lines and (through the patented Eliminator) expels them continuously from the system. It is extremely simple, with *no* filter pads to replace — no bearings or whirling gadgets — no trap or vent cock to be opened at frequent intervals. It's *automatic.*

IMMEDIATE DELIVERY

All popular sizes are available for immediate delivery — *at less than pre-war prices!* Write today for a copy of the valuable and comprehensive bulletin "Clean, Dry Compressed Air."

THE LEAVITT MACHINE COMPANY

130 E. River Street, Orange, Mass.

S-72

Dexter AUTOMATIC SEPARATORS

ALSO MAKERS OF DEXTER VALVE RESEATING MACHINES
ATHOL PLUMBING SUPPLIES AND DEXTER LATHE CHUCKS.



BUY ALL THREE FOR ONLY $6.00

or Any COMBINATION at PROPORTIONATE SAVINGS

COMPRESSED AIR DATA (Fifth Edition): 408 pages on the theory and practice of compressed-air engineering.

CAMERON HYDRAULIC DATA (Eleventh Edition): 240 pages on hydraulics, water data, miscellaneous liquids, steam data, electric data, and miscellaneous data.

CAMERON PUMP OPERATORS' DATA (First Edition): 170 pages of practical information for the man who installs, operates or services centrifugal pumps.

Fill out the coupon and mail it today. Be certain to check the group of books wanted.

PRICE INDIVIDUAL BOOKS PER COPY

Compressed Air Data.....$3.00
Cameron Hydraulic Data.....$3.00
Cameron Pump Operators Data.....$2.00

COMPRESSED AIR MAGAZINE, 942 Morris Street, Phillipsburg, New Jersey, U. S. A

Please send me:

- ☐ Compressed Air Data, Cameron Hydraulic Data and Cameron Pump Operators' Data.....All three for $6.00.
- ☐ Compressed Air Data and Cameron Hydraulic Data.....Both books for $5.00.
- ☐ Cameron Hydraulic Data and Cameron Pump Operators' Data....Both books for $4.50.
- ☐ Compressed Air Data and Cameron Pump Operators' Data.....Both books for $4.50.
- ☐ Enclosed is (money order) (check) for $.....) ☐ Send books C.O.D. I understand that the books will be sent me postpaid, and that they may be returned within 10 days if not satisfactory.

Name .....

Company .....

Street No. .....

City .....State.....Country .....

SET for the life of the line



it's a fairbanks valve

0236—200 lbs. S. W. P.

UNION BONNET BRONZE GATE VALVE

Engineered in every detail to provide maximum service under the toughest operating conditions. Hard nickel alloy seats and wedges resist corrosion. Union Bonnet (with heavy octagonal nut) assures great strength, 100% tightness under pressure, yet permits quick, easy dismantling for cleaning and inspection. To eliminate high maintenance costs, shutdowns or other operating problems, install Fairbanks Union Bonnet Bronze Gate Valves. Recommended for steam (200 lbs.), water, oil or gas. Sizes ½" through 2". The Fairbanks Company, 393 Lafayette St., New York 3, N. Y.; 520 Atlantic Ave., Boston 10, Mass.; 15 Ferry St., Pittsburgh 22, Pa.; 748 M & M Bldg., Houston 2, Texas.



232

UNION BONNET BRONZE GATE VALVE

Non-Rising Stem.

All parts interchangeable with Rising Stem Type. Sizes ½" through 2".

American industry flows through fairbanks valves

RHOADS

Tannate-Rockwood



SHORT CENTER DRIVE

ASSURES YOU MORE PRODUCTION

1. **PROVIDES CONSTANT, UNIFORM SPEED** — higher hourly production, more uniform work, fewer shutdowns, less spoilage.
2. **CORRECT BELT TENSION** — automatically maintained, regardless of load fluctuation.
3. **SIMPLE, COMPACT, EASY TO INSTALL** — and they require a minimum of attention and maintenance.
4. **HIGH OVERLOAD CAPACITY** — pivoted motor base provides greater load capacity. Belt is automatically tightened when the load increases, and as the load decreases the tension on the belt and bearings is reduced.

TANNATE Belt operates smoothly at full capacity . . . carries full load when damp . . . withstands high temperatures, water, machine oils and many dilute chemicals. Pivoted motor base can be used with small or large motors . . . drives equally well horizontally, vertically, or suspended from the ceiling. For details about this dependable, reliable drive, write

PRODUCERS OF FINE LEATHER FOR 245 YEARS

J. E. RHOADS & SONS

35 NORTH SIXTH ST., PHILA. 6, PA.

NEW YORK • CHICAGO • ATLANTA

ESTABLISHED 1702



Inside Knowledge on Lubrication Problems

—WEAR—

This is One of a Series of Messages on Common Problems in Your Plant

No Punches Pulled Here!

SEE THE PISTON inside this stoper? It's flying back and forth in the cylinder over 2,000 times per minute, punching the hammer with every stroke.

Imagine the job that lubricating oil must do to protect the rifle nut, the bar piston and the cylinder walls from wear. Here's a spot where you really need strong oil films to prevent wear and maintain tight seals.

Gargoyle Almo Oils provide both tenacious films and a combination of other properties necessary for this air tool job. They flow quickly and evenly to all working parts and stay on despite the washing action of water from condensation or leakage. Highly stable, they keep valve-clogging deposits down to a minimum.

Get these proved Socony-Vacuum products in air tools for *extra* protection that means *extra* production.

SOCONY-VACUUM OIL CO., INC.
and Affiliates: Magnolia Petroleum Company
General Petroleum Corporation

GARGOYLE Lubricants

SOCONY-VACUUM

Socony-Vacuum Correct Lubrication

FOR EVERY MACHINE . . . EVERY OPERATING CONDITION